



# Lloyd's Register of Shipping.

(UNITED WITH THE BRITISH CORPORATION REGISTER)

18, NIHON OH-DORI NAKA-KU,

(CHARTERED BANK BUILDING)

(P. O. BOX NO. 228),

YOKOHAMA, JAPAN

17th December, 1958

RECEIVED

22 DEC 1958

reference

Dear Sir,

Also "RIYASHI-MARU" (F.E. Rpt. No. 2711)

We thank you for your letter of the 11th ult., regarding the above vessel and your remarks have been carefully noted.

Regarding the points raised we now confirm or clarify as follows:-

- (1) Approved equipment numeral is 99,273.53, as approved by Kobe Office, please see the calculation sheet, forwarded herewith, and we shall be glad if you will kindly return this sheet after your perusal.
- (2)a. As this ship has no dry cargo hold or space, no cargo hatch was provided.
- b. One each small hatch for boatswain stores and provision store were fitted with the following particulars:-

	<u>Rope Hatch</u> (Fore Boatswain) Store	<u>Rope Hatch</u> (Poop Boatswain) Store	<u>Provision Hatch</u> (Poop)
Size	570mm x 620mm	570mm x 620mm	970mm x 970mm
Coaming (Height x thickness)	610mm x 11mm	460mm x 11mm	460mm x 11mm
Cover & thickness	Steel, 7mm with 2 Hinges & 5 toggles	Steel, 7mm with 2 Hinges & 5 toggles	Steel, 7mm with 2 Hinges, & 8 toggles

- c. One round hatch was fitted to each cargo oil tanks, the particular as follows:-

1200mm dia. 12mm thick coaming 325m/m high.  
secured with hinged steel cover 12.7mm thick.

A/R

012744-012751-0021 1/2

Lloyd's Register  
Foundation



*Noted Report omitted.  
 Equipment calculation sheet should be requested  
 (Copy sent in box)  
 R.A.G.  
 20/2/58*

© 2021



Lloyd's Register Foundation



(UNITED KINGDOM OF GREAT BRITAIN)  
 IN THE HIGH COURT OF JUSTICE  
 IN THE MATTER OF THE  
 LLOYD'S REGISTER  
 (INCORPORATED IN GREAT BRITAIN)  
 (BY ORDER OF THE COURT)  
 LLOYD'S REGISTER  
 (INCORPORATED IN GREAT BRITAIN)

5000 (1/1/58) 1/1/17

Do. of spec  
 between I  
 and Upp



YD'S REGISTER OF SHIPPING,  
YOKOHAMA, JAPAN

Continuation Sheet No. 2

17th December, 1958

- d. One round hatch was fitted to each Nos. 2 & 3  
O.F. Tanks (P. & S.), O.F. Settling Tanks (P. & S.)  
and Forward and After Cofferdams (P. & S.), the  
particulars as follows:-


650mm dia, 12mm thick coaming 610mm. minimum  
height, secured with hinged steel cover 12.7mm  
thick.

(3) 17 bulkheads are fitted.

The above discrepancies and omissions are  
regretted and trust the information now given will be in  
order.

We are,

Yours faithfully,

  
For The Surveyors

The Secretary,  
LONDON

Enclosure - Calculation of Equipment Number

KN/hy



© 2021

DISCLOSED

SECTION

Lloyd's Register  
Foundation

No. 949

00212/m