

16. APR 1963

Ship's Name ~~SS/MS~~ "PADEREWSKI" Gross tons 7230
 Is there a rpt. 9? No Port NANTES Rpt. No. 963
 No. of visits 3 First date 30-3-63 Last date 4-4-63
 Interim Cert. issued & copy herewith? Yes Damage rpt. issued & copy herewith? No Last rpt. (H.Q. only)
 Date of completing rpt. 8-4-63 Surveyed at, if different from Port above LA PALLICE
 Surveyed afloat and/or in D.D. AFLOAT Last date of examination in D.D. -
 Has a Load Line Survey been held? No Freeboard Marks verified No

MAY 1963

13463 B B

State which additional Rpt. 8 is attached: (Cont.) (PS) (DR) (EO) (Rig)

Survey fees - Damage fee 400,00 F. Expenses 257,00 F.

S.A. fee 70,00 F.

action taken or recommended should be described fully under "defects & repairs". When any part has been subjected to pressure test this should be stated.

I have surveyed the above ship in accordance with the Rules for damage, stated to have been caused by contact with ice during voyage from GDANSK to BILBAO on 11th & 12th March 1963.

Items now surveyed are detailed on this report. All were found or placed in good condition unless otherwise stated.

Find:- Side shell seam & frame rivets started & leaking in way of No 4 Hold P & S.

Work done for temporary repair:- Approx. 220 side shell rivets above W.L. (lightship) ring welded. 4 frames & part shell seam below W.L. (PS) & 4 frames & part shell seam (S.S.) sealed by welding & injected with composition. All examined on completion & found satisfactory & it is recommended that this item be specially examined & dealt with as found necessary next drydocking.

Conditions of class:- Nothing done at this time, S.R.L. appendix:- Nothing done at this time.

I recommend that this ship remain as classed with/without fresh record of dry docking subject to defective rivets in shell plating in 4th & 5th strakes below sheer in way of No 4 Hold P & S being examined & dealt with as found necessary next dry docking, and to any outstanding conditions of class being dealt with as previously recommended.

(Where conditions of class are recommended to be retained, imposed, amended or deleted, particulars must be stated above and on the interim certificate.)

Malcolm Smith for self
+ T.S.L.

M.M. SMITH & T.S. BRIGHTON
Surveyors to Lloyd's Register of Shipping

Date of Committee MONDAY 13 MAY 1963

Minute

As now subject not
Note B/B duty.

ALSO FOR
 SPL FOR
 TRO
 SRL
 POSTING
 HEADER
 CERT



Lloyd's Register Foundation

3 rpts for chg

7210 - 008210 - 967210