

CLOSED

Rpt. C. 11 (Contd.)

Index No.
(For London Office use)

LLOYD'S REGISTER OF SHIPPING

BOSEP 1963

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name M.V. "PADEREWSKI" Official No. 15

Port of Registry G D Y N I A

This ship has been under survey at G D A N S K

on 8 th March 196³ and the following alterations to the conditions of

assignment of loadlines have now been effected/found:—

The tonnage hatch is provided with two-part steel cover with joint secured from below by hook screwed bolts spaced less than 24 inches.

The tonnage hatch scuppers blanked off efficiently.

The Load - lines appropriate to the Closed Shelter Deck condition, were marked by punching, painted and verified, and previous marks obliterated.

The tonnage openings in the tonnage hatch bulkhead and in tweendeck bulkheads are closed by jointed steel plates and bolted with screws spaced not more than 12 inches apart.

The Vessel has been converted to the Closed Shelter Deck Condition.

M. Chuchla
M. CHUCHLA

Surr. to L.R. of Shipping

A copy of this Report has been placed on board.



© 2021

Lloyd's Register
Foundation