

LLOYD'S REGISTER OF SHIPPING

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name M.V. "PADEREWSKI"Official No. 24 15Port of Registry G D Y N I AThis ship has been under survey at G D A N S Kon 8 th March196 ³ and the following alterations to the conditions ofassignment of loadlines have now been ~~effected~~ found:—

The tonnage hatch is provided with two-part steel cover with joint, secured from below by hook screwed bolts spaced less than 24 inches.

The tonnage hatch scuppers blanked off efficiently.

The Load - lines appropriate to the Closed Shelter Deck condition, were marked by punching, painted and verified, and previous marks obliterated.

The tonnage opening ~~qq~~ in the tonnage hatch bulkhead and in tweendeck bulkheads are closed by jointed steel plates and bolted with screws spaced not more than 12 inches apart.

The Vessel has been converted ~~e~~ to the Closed Shelter Deck Condition.

Noted
9/4/63

A copy of this Report has been placed on board.