

# Lloyd's Register of Shipping.

Ship's Name

~~"GREEN GABLES PARK"~~

WORLD TROTTER

Official No. 174164

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
in June 1943.

Alterations:-

D.E.M.S. cabins forward of No. 19 W.T. bulkhead in No. 5. tween  
decks port and starboard removed. Three port lights and one ventilator  
(6" dia.) either side removed and openings in way efficiently closed  
with welded plates and proved tight.

Access doors in No. 19 bulkhead port and starboard closed with  
bolted plate in accordance with North Van Ship Repairs Ltd.  
drawing (N.V.L.29)

Hose tested and proved tight.

Forward magazine in No. 1 tween deck removed together with access  
trunkway and hinged steel door. Deck aperture closed with insert  
plate efficiently welded in place.

Hose tested and proved water-tight.

*D. J. Archibald*

Surveyor to Lloyd's Register

Vancouver, B.C.

16th October, 1945.

*Tested*

*ged.*  
11/12/45

