



STEM 6" x 6" x 3/8 ANGLE  
 STERNPOST 6" x 1 1/4"  
 RUDDER STOCK 4 1/2 DIA.

- EQUIPMENT
- 2- 1000 LBS STOCKLESS ANCHORS [BOWERS]
  - 1- 336 LBS. ANCHOR [EX. STOCK] [STREAM]
  - 165 FATHOMS 1" STUD LINK CHAIN CABLE
  - 90 FATHOMS 5/8" C. HEMP HAWSER
  - 45 FATHOMS 2 1/2" C. F.S.W [STREAM WIRE]
  - 75 FATHOMS 2 1/2" C. F.S.W [TOWLINE]

DIMENSIONS

LENGTH B.P.	156' 0"
BREADTH AT DK	32' 0"
BREADTH AT BOTTOM	24' 0"
DEPTH MLD.	11' 9"
DRAFT MAX.	10' 0" [APPROX.]

"SAULT AU MOUTON"  
 LLOYDS. CLASS#00A.1 FOR SERVICE ON RIVER ST. LAWRENCE  
 AND TO WEST END OF ANTICOSTI ISLAND.

APPROVED  
 NOV 30 1911  
 LLOYD'S REGISTER OF SHIPPING  
 NEW YORK

The electric welding must be done with an approved electric, and the reinforcement of the Society's RULES FOR THE APPLICATION OF ELECTRIC ARC WELDING FOR SHIP CONSTRUCTION must be carried out.

ALEX. C. CAMPBELL  
 CONSULTING NAVAL ARCHITECT  
 70 ST. PAUL STREET  
 QUEBEC, QUE.

GEO. T. DAVIE & SONS LTD.  
 LAUZON, QUE.  
 HULL No 34  
 MIDSHIP SECTION

Job No.	34-1	1/2 INCH = 1 FOOT
DATE	Nov. 21st 11	34-1B



'CAP SAUMON'

M/M.13410'



© 2021

Lloyd's Register  
Foundation

013409-013416-0047