

COPY.

LLOYDS REGISTER OF SHIPPING
CADIZ.

2nd June, 1934.

Dear Sir,

In reply to your letter of the 25th ultimo, with reference to the reports Nos. 1421 and 1422 on the machinery of the m.s. "CAMPECHE" and "CAMPERO", I have received from Mr. Black and now state the information desired, viz:- ballast pump, steam driven 10" x 11" x 11" 200 tons per hour, 8" suction and discharge. 2 power bilge pumps, electric, 60 tons per hour 1550 revs. 1 ballast pump in forward pump room 8" x 8" x 10" 70 tons per hour, steam driven.

Sizes of suction connected to both main bilge pumps and auxiliary pumps in machinery spaces are as follows:-

Ballast pump direct bilge suction 8".
" " bilge main " 4½".

Bilge pumps worked from main engines, one each engine, dia. 140 mm. stroke 320 mm.

No. 1 bilge pump direct bilge 3½".
" " bilge main 4".
oil cofferdam 3½".

No. 2 bilge pump direct bilge 3½".
" " bilge main 4".
oil cofferdam 3½".

Starboard main engine bilge pump main bilge line 5".
Port " " " " " 5".

direct bilge suction 1 - 8" and 2 - 3½".
Suctions on main bilge line 10-3½" and 2-4".

Aft cofferdam. 2-3½".
Forward cofferdam 2 - 3½".
Centre cofferdam 1 - 2½".
Dry tank 1 - 2½".

The forward ballast pump in forward pump room has the following suction:-

Forward hold suction..3".
Forward cofferdam 3".
Pump room suction 3½".
Chain locker.....2½".
Store room forward 2½".

The boilers are placed on a platform deck at aft end of engine room and are 5,500 mm above tank top and 1450 mm. from top of shell to bottom of oil settling tank.

The name of the manufacturer of the steel for the boilers of the "CAMPECHE" will be stated on the Valencia Report No. 194.

The number of visits will be paid to the boilers of the "CAMPECHE" is 12 and the dates of first and last visits to the boilers of the "CAMPERO" are 1st, 24th August 1933 and

013671-013677-0557 112

DISCLA
1 SECT
No.

© 2021
Lloyd's Register

COPY.

-2-

last 22nd April, 1934. and the total number of visits is 12.

The plan showing the arrangement of suction pipes is returned herewith and Mr. Black states that this is the only plan he had in his possession.

I am, Dear Sir,
Yours faithfully,
(s) R. LANGLANDS.

The Secretary,
London.



© 2021

Lloyd's Register
Foundation

0057 2/2