

# REPORT ON ELECTRICAL EQUIPMENT.


(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office.....

12 JAN 1944

Date of writing Report.....19..... When handed in at Local Office.....11 JAN 1944..... Port of.....HULL.....  
 No. in Survey held at.....GOOLE..... Date, First Survey.....18.8.43..... Last Survey.....4.1.1944.....  
 Reg. Book..... on the.....M.V. "AMENITY"..... Tons {Gross.....881.....  
 Net.....462.....  
 Built at.....Goole..... By whom built.....Goole S.B. & R. Co. Ltd., Yard No.....395..... When built.....1944.....  
 Owners.....F.T. Everard & Sons. Ltd. Port belonging to.....London.....  
 Electrical Installation fitted by.....Humber Electric Co. Ltd. Contract No.....-..... When fitted.....1944.....  
 Is vessel fitted for carrying Petroleum in bulk.....No..... Is vessel equipped with D.F.....No..... E.S.D.....No..... Gy.C.....No..... Sub.Sig.....No.....

Have plans been submitted and approved.....Yes..... System of Distribution.....two wire..... Voltage of supply for Lighting.....220.....  
 Heating.....220 Power.....220 Direct or Alternating Current, Lighting.....D.C. Power.....D.C. If Alternating Current state periodicity.....- Prime Movers,  
 has the governing been tested and found as per Rule when full load is suddenly thrown on and off.....Yes..... Are turbine emergency governors fitted with a  
 trip switch as per Rule.....- Generators, are they compound wound.....Yes..... are they level compounded under working conditions.....Yes.....  
 if not compound wound state distance between generators.....10..... and from switchboard.....- Where more than one generator is fitted are they  
 arranged to run in parallel.....No..... are shunt field regulators provided.....Yes..... Is the compound winding connected to the negative or positive pole  
 negative..... Have machines over 100 kw. been inspected by the Surveyors during manufacture and testing.....- Have certificates of  
 test for machines under 100 kw. been supplied.....Yes..... and the results found as per rule.....Yes..... Are the lubricating arrangements and the construction  
 of the generators as per rule.....Yes..... Position of Generators.....Engine Room No. 1 starboard, No.2 port side.....  
 is the ventilation in way of generators satisfactory.....Yes..... are they clear of inflammable material.....Yes..... if situated  
 near unprotected combustible material state distance from same horizontally.....- and vertically.....- are the generators protected from mechanical  
 injury and damage from water, steam and oil.....Yes..... are the bedplates and frames earthed.....Yes..... and the prime movers and generators in metallic  
 contact.....Yes..... Switchboards, where are main switchboards placed.....Engine room forward bulkhead, port side.....  
 are they in accessible positions, free from inflammable gases and acid fumes.....Yes..... are they protected from mechanical injury and damage from water, steam  
 and oil.....Yes..... if situated near unprotected combustible material state distance from same horizontally.....- and vertically.....- what insulation  
 material is used for the panels....."Syndanyo"..... if of synthetic insulating material is it an Approved Type.....Yes..... if of  
 semi-insulating material (slate or marble) are all conducting parts insulated therefrom as per Rule.....- Is the frame effectually earthed.....Yes.....  
 Is the construction as per Rule.....Yes..... including accessibility of parts.....Yes..... absence of fuses on the back of the board.....Yes..... individual fuses  
 to pilot and earth lamps, voltmeters, etc.....Yes..... locking of screws and nuts.....Yes..... labelling of apparatus and fuses.....Yes..... fuses on the "dead"  
 side of switches.....Yes..... Description of Main Switchgear for each generator and arrangement of equaliser switches.....One overload circuit  
 breaker for each generator.....  
 and for each outgoing circuit.....Double pole quick break knife switches & double pole fuses for all  
 principal circuits, single pole knife switches & double pole fuses for accomodation etc.....  
 Are compartments containing switchboards composed of fire-resisting material or lined as per Rule.....Yes..... Instruments on main switchboard.....two  
 ammeters.....two..... voltmeters.....-..... synchronising devices. For compound machines in parallel is the ammeter connected on the pole opposite to the  
 equaliser connection.....- Earth Testing, state means provided.....Lamps coupled to earth via switches and fuses.....  
 Switches, Circuit Breakers and Fuses, are they as per Rule.....Yes..... are the fuses an approved type.....Yes..... are all fuses labelled as  
 per Rule..... If circuit breakers are provided for the generators, at what overload current did they open when tested.....20%..... are the reversed current  
 protection devices connected on the pole opposite to the equaliser connection.....- have they been tested under working conditions, and at what current  
 did they operate.....- Joint Boxes, Section Boards and Distribution Boards, is the construction and position as per Rule.....Yes.....  
 Cables, are they insulated and protected as per the appropriate Tables of the Rules.....Yes..... if otherwise than as per Rule are they of an approved type.....-  
 state maximum fall of pressure between bus bars and any point under maximum load.....4V..... are the ends of all cables having a sectional area of 0.04  
 square inch and above provided with soldering sockets.....Yes..... Are paper insulated and varnished cambric insulated cables sealed at the ends.....Yes.....



© 2021

Lloyd's Register  
Foundation

013917-013926-0016/2



