

"EMPIRE WILSON"

The following particulars have been extracted from Glasgow Report No. 68889, attached to Wreck Reports of the m.s. "STATIRA".

"Waste heat donkey boiler examined internally and externally together with safety valves, doors and mountings and found or placed in good working order. Boiler afterwards hydraulically tested to 150 lbs. per sq.in. and found sound. Boiler was stamped:-

LLOYD'S RE-TEST

150 lbs.

W.P. 120 lbs.

A.J.B. 5.10.42

Repairs:- Boiler cleaned, tubes scraped and a number renewed; mountings reconditioned; smoke box refitted. Boiler steamed out and degreased.

On completion of repairs, the engine was assembled on test bed in shop and tests were carried out under full load conditions for six hours with satisfactory results. The engine and single ended boiler have been sent to Dalmuir for storage to await allocation. The waste heat boiler has been allocated to Messrs. Barclay Curle & Co., Ltd., for installation in Messrs. Chas. Connell & Co's Yard No. 446 in conjunction with their Eng. No. E.W. 142. "EMPIRE WILSON". "



© 2021

Lloyd's Register
Foundation

01445104462-0224