

For Reports Dept., Work.

"TREVANION" Messrs LITHGOWS YARD No.985

Rule Dimensions:- 425.33 x 57.75 x 29.08 to 2nd deck  
38.17 to upper deck.

Class:- 100A1 "With freeboard".

This ship is of the C.S.S. type, but the scantlings are suitable for a draught 18" in excess of that contemplated by the Rules for a Complete Superstructure Ship.

When the plans of watertight bulkheads was approved the Surveyors were informed that as the scantlings of the hold bulkheads have been based on a height to the 2nd deck, a suitable notation will require to be made in the Register Book regarding the Bulkheads.

The Surveyors were also informed with reference to the Builders' proposal to fit tonnage openings in the bulkheads in the upper tween decks, that it is understood that in the case of new ships the Admiralty desire all bulkheads to be intact but that where openings are necessary by reason of the nature of the cargo to be carried they will insist upon hinged watertight doors being fitted.

There is nothing further in the correspondence affecting the First Entry Report.

26.1.44.



*[Handwritten signature]*

© 2021

Lloyd's Register Foundation

014887 - 014898 - 0324