

"L.C. 9"

26 OCT 1949

This vessel was built in 1940-12 and classed LOCAL Salvage Lighter until 9.48 when the vessel was deleted from the Register Book.

Correspondence received at that time indicated that the vessel would be used for experimental work.

A PERIODICAL SPECIAL SURVEY (A) was held 4.46.

The class was subject to 15 fathoms of chain cable being supplied.

Reclassification is now desired.

IT IS SUBMITTED the PLYMOUTH Surveyors in answer to their letter dated 20.10.49 be informed that a PERIODICAL SPECIAL SURVEY (B) should now be held. They should satisfy themselves that no major alterations have been effected to the original structural arrangements, and report on the condition of the inner surface of bottom plating, with particular reference to the coating (cement, bitumastic, etc.).

They should also be informed the vessel's class was subject to 15 fathoms of chain cable being supplied.

The equipment of anchors and chain cables originally proposed consisted of two stockless bower anchors of 19-20 cwts, and 240 fathoms of 1.3/8" diameter chain cable. This was approved as the vessel was also to have special equipment of salvage gear which included four anchors each of 70 cwts. as well as wires in excess of the Rule requirements, but details of the equipment now on board should be forwarded for the consideration of the COMMITTEE.

The following parts require to be opened up for the machinery portion of the survey:-

Boiler Survey to be held,
All pumps, pumping arrangements, ~~Condenser~~
auxiliaries, sea connections to be
examined and electrical equipment
to be examined and megger tested and
steam pipes to be tested.

It is concluded that no major alterations have been effected to the machinery since originally fitted.

Y. R. R.



JmB
24.10.49
Boyle

Lloyd's Register
Foundation

01524 015232-0306

For Ken Harris
to write PLY

PLC

1.11.49



© 2021

Lloyd's Register
Foundation