


COPY

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Port NOTTINGHAM. June 27th/55.

Ruston & Hornsby Ltd., Engine No. 393591.

Type 3VSHZ.

71412/11/550877. B.10055.

This is to Certify that

T. D. Scott

the undersigned Surveyor to this Society did at the request of

Messrs. Ruston & Hornsby Ltd., Lincoln.

attend at their works for the purpose of examining and testing
 One Heavy Oil Engine as noted below, manufactured to the order of:-
 Messrs. Lindeteves N/V, Amsterdam and intended for auxiliary purposes.

Particulars of the engine are as follows:-

Engine Number.....	393591.
Type	VSHZ.
Number of Cylinders	3.
Diameter of Cylinders	4.1/2"
Stroke	4.1/2"
Maximum Pressure	850 lbs.
Mean Indicated Pressure	104.
Brake Horse Power	22.50.
Revolutions per Minute	1000.
Span of Bearings	5.7/16"
Diameter of Journals	2.3/8"
Diameter of Crankpins	2.3/4"
Breadth of Webs	2.3/4"
Thickness of Webs	1.3/8"

This engine has been built under Special Survey, in
 accordance with the Approved Plans and Rules of the Society,
 materials and workmanship being good.

On completion, the above machinery was tried in the
 shops under working conditions with satisfactory results.

For purposes of identification the cylinder block and
 crankshaft were stamped thus:-

LLOYD'S TEST
 50 lb./sq. in.
 6.6.55. TDS.
 Engine No. 393591.

LLOYD'S TEST
 LL.10209. AS.1406A.
 No.

Engineer Surveyor to
 Lloyd's Register of Shipping.

Fee:— £5. *L*

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."