

Her Masts, Yards, &c. are in Good condition, and sufficient in size and length.

She has SAILS.

N°.	
2	Fore Sails,
2	Fore Top Sails,
2	Fore Topmast Stay Sails,
1	Main Sails,
2	Main Top Sails, and well found in other sails

CABLES, &c.

Fathoms.	Inches.
240	1 1/8
75	7 1/2
75	6
75	5 1/2
45	7 1/8

ANCHORS, and their weights.

3	Bowers,
1	Stream,
2	Kedges,

Her Standing and Running Rigging is all new sufficient in size and Good in quality.

She has a Long Boat and Jolly Boat Gig

The present state of the Windlass is Good Capstan Good and Rudder Good
with Bow & Hawse's Patent Purchase Two lead pumps Good

General Remarks Statement and Date of Repairs.

Laid on in February, and launched 19th October, 1841. Surveyed at the three prescribed stages, and at other times specially, while building. All the Frame Welsh and English Oak, (with the exception of seven Midship floors, and ten straight first fatoocks, which are American Oak,) of good quality, and well squared. Built wholly in Frame; Shifts of timber good; Cross Chocks, butt lipped, full Butts and Scarphs. Planking and ceiling of good quality, and well wrought, shifted three between. Shear stakes and plank shears, of East India Teak; and three stakes of the Wales, of African Oak. Number of Beams, and fastening and Spars, as described. Two Iron pointers, and an Iron crutch aft. Yellow Metal Bilge, Butt and footwale, bolted, through, and clenched on rings. Nelson bolts Yellow Metal, through each floor, and clenched on rings, on Main Web. She is well finished, and the materials and workmanship throughout, rather superior for a ship of her class. Her stores and furnishings are complete, and of the best description.

1841/293

1st Class
2nd Hand
No. 1
SA 2

If Sheathed, Doubled, Felted, or Coppered Yellow Metal over paper to When last done the Wales, in Oct. 1841.

I am of opinion this Vessel should be Classed "8A1."

The Amount of the Fee.....£ 5 : - : - is received by me,

Special£ 20 : 3 : -

Wm R. Parry

Committee's Minute 16th Nov 1841

Character assigned A 1 for 8 Years

2

Her Masts, Yards, &c. are in Good condition, and sufficient in size and length.

She has SAILS.

No.	Fathoms.
2	Fore Sails,
2	Fore Top Sails,
2	Fore Topmast Stay Sails,
1	Main Sails,
2	Main Top Sails,
	and well found in other sails

CABLES, &c.

Fathoms.	Inches.	No.
240	Chain 1 $\frac{1}{2}$ 81 $\frac{1}{2}$ 6	3
75	Hempen Stream Cable 7 $\frac{1}{2}$	1
75	Hawser 6	2
75	Towlines 5 $\frac{1}{2}$	
45	Warp Stream Chain 7 $\frac{1}{8}$	
	All of <u>Good</u> quality.	

ANCHORS, and their weights.

Bowers,

Stream,

Kedges,

Her Standing and Running Rigging is all new sufficient in size and Good in quality.

She has a Long Boat and Jolly Boat Gig

The present state of the Windlass is Good Capstan Good and Rudder Good
with Iow & Fawcett's Patent Purchase Two lead pumps Good

General Remarks Statement and Date of Repairs.

Laid on in February, and launched 19th October, 1841. Surveyed at the three prescribed stages, and at other times specially, while building. All the Frame Welsh and English Oak, (with the exception of seven Midship floors, and ten straight first fatoocks, which are American Oak,) of good quality, and well squared. Built wholly in Frame; Shifts of timber good; Cross chocks, butt lipped, full Butts and scarphs. Planking and ceiling of good quality, and well wrought, shifted three between. Shear stakes and plank shears, of East India Teak; and three stakes of the Males, of African Oak. Number of beams, and fastening and spaces, as described. Two Iron pointers, and an Iron catch aft. Yellow Metal Bilge, Butt and forecastle bolted, through, and clenched on rings. Nelson bolts Yellow Metal, through each floor, and clenched on rings, on Main Deck. She is well finished, and the materials and workmanship throughout, rather superior for a ship of her class. Her stores and furnishings are complete, and of the best description.

1006
Lloyd's Register of British
and Foreign Shipping.
Greenock, 19 March 1842

Charles Graham Esqre

Sir:

Please receive herewith
Reports of Survey numbered 1157 & 1163
which I hope will be found correct.

And I beg to Report, that I have ascertained that the New Bangaloo "Top" Report p. 1096, has proceeded on her way to Calcutta, forty fathoms of Chain Cabin short. The length required by the Rules were ordered, and reported by me, on the word of the master, to be paid on board. The Furnisher now informs me, that when the Cables were being sent to the ship, Capt. Crawford would not allow him to send more than 200 fathoms, as I take every means in my power to ascertain, that the ships are furnished as reported. This is an occurrence that can seldom take place. I have therefore to submit, whether this ship, should not be put on figure 2. in the Register Book.

Very respectfully
Sir

Your most Obedient Servt
John R. Gammie

If Sheathed, Doubled, Felted, or Coppered

I am of opinion this Vessel should be Classed

for The Amount of the Fee £ 5 : -

Special £ 20 : 3

Committee's Minute 16th

Character assigned

