

Her Masts, Yards, &c. are in Good condition, and sufficient in size and length.

She has SAILS.

N°.	Fathoms.	
2	Fore Sails,	270
2	Fore Top Sails,	70
2	Fore Topmast Stay Sails,	90
1	Main Sails,	90
2	Main Top Sails,	75
	and well found in other Sails	

CABLES, &c.

	Inches.	N°.
Chain	17. & 1½	3
Hempen Stream Cable	10	1
Hawser	6½	2
Towlines	4¾	
Warp .. Steam Chain	1½	
All of <u>Good</u> quality.		

ANCHORS, and their weights.

Bower,

Stream,

Kedge,

Her Standing and Running Rigging all new sufficient in size and Good in quality.

She has a Long Boat and Jolly Boat and Cutter.

The present state of the Windlass is Good Capstan Double Winch and Rudder Good Pumps Four Lead, good
With Gladstones Patent Purchase

General Remarks Statement and Date of Repairs.

Laid on in February 1843. Launched 6th January 1844. Surveyed at the
three prescribed period, and at other times specially, while building. Frame Welsh & English
oak, of good quality, and all very well squared. Built wholly in frame. Shifts of timbers
good. Cross chocks Butt tipped, and full Butts douvelled. Plank outside, and ceiling, of
very good quality, well wrought, and shifted three between. Two plank of five inch wrought
on, inside, in way of second futtock heads, and yellow metal boltes into heads and heels of
timbers, through also clenched on rings. Number of Beams, Spaces, and fastenings, as described,
and the Beams hooped at the extrem ends, to prevent splitting in bolting. Yellow Metal Pipe
and Butt boltes through, and clenched on rings. She has two pair of pointers, and a cutter
aft, all of iron. The Wing and Rider transoms, are diagonally iron knees to the sides. She is very
well finished; the workmanship throughout very good, and her stores and furnishings com-
plete, and of the best description.

If Sheathed, Doubled, Felted, or Coppered Coppered over paper from Nail to Waterline When last done in January 1844.
Lower Shire of Wales.

I am of opinion this Vessel should be Classed 12 M.I.

The Amount of the Fee.....£ 5: u : u is received by me,

Special£ 27: 8: u

John R. Canning

Committee's Minute 6th February 1844

Character assigned 1 for 12 Years

W.H.

© 2021

Lloyd's Register
Foundation