





## SURVEYOR'S REMARKS.

**Timbering.** *Timbering nearly all of English Oak some Continental floors.*  
**The Quality,** *Beams & knees English all well squared and good work.*  
**Squaring, and** *Mananship.*  
**Workmanship.**

**Planking.**  
**Outside and Inside** *Outside of bottom Elm. to Left Mark Ash. outside -*  
**Quality, Edging,** *solank. Mostly of English with some Danish oak inside.*  
**and Workmanship.** *celing nearly all English good workmanship.*

**Fastenings.** *Entirely Copper fastened below the Wale, butts double*  
**If Sheathed,** *bottles but not through nor clenched - beys bottled through*  
**Doubled, or** *with Copper & clenched upper & Lower Deck beams all well bound*  
**Felted.** *with double wood lagging knees & they join to Lower Deck beams*  
*4 Iron hanging knees on each side to upper Deck beams and*  
*four burst hooks below the Deck single bottom.*

**Repairs.** *Has just had an overhaul in Dock Copper Stuffed and*  
*solank all chipped down from Wale to Keel spind in*  
*both quarters & frame sound Mostly retrenched & caulked*  
*new Watertway & upper Deck beams abround last year.*

**General Observations** *A very substantial Well built vessel of excellent Material.*  
**and Opinion as** *Large scantling & good workmanship sound and in good*  
**required by the** *repair Decks, Watertway, hatch coverings & beam -*  
**Instructions.** *fastenings all tight and good. Out & inside plank and*  
*trunnels all in good order. Moulds well fitted and*  
*evidence well hung and is in a fit condition for the*  
*safe conveyance of Cry & Peushall Cargoes.*

The Amount of the Fee, £ 1 : 1 : - is received by me.

Committee Minute 16 June 1835

Character assigned Fi

*David Lighton*

*Wm. L. L.*



© 2009

Lloyd's Register  
Foundation