

REPORT of SURVEY for REPAIRS.

No. 773 Survey held at Glasgow Date 2^d September 1853
 on the Bonquo Nile Master Henry Leighton
 Tonnage 387 Built at Glasgow When built 1846
 By whom built 380 W. H. Rowan & Co Owners Potter Wilson & Co
 Port belonging to Glasgow Destined Voyage Melbourne
 If Surveyed Afloat or in Dry Dock Patent Ship

Last Survey, No. 11152 Port Liverpool Classed 10 A 1

REPAIRS *Of Damage, At Present Shipped the Yellow Metal Sheathing and Cleaned the Bottom; Renewed all the Out and In Hold Beam Knee and Shelf Bolts with Yellow Metal below the Wale and Iron above, Put in Six Pairs of Additional Diagonal Iron Ribs in the Hold Extending from the Beams to below the Turn of the Bilge Bolted through and Clenched, Two with Hanging Knee Connected, refastened the Ciling in the Hold with Iron Dump Bolts and Wedged all the open Seams; New Ribs Keelson Obviate the Mizen Step; Renewed the Head Rail and repaired the Bulwark and Rail. Unrigged the Mizen Mast; New Fire Guard Caulked from Keel to Wale and Keelheated with Yellow Metal to the Wale over Paper Below and Felt above*

Present Condition of the		Treenails		Windlass and Capstan	
Decks	Good	Breasthooks and Stemson	do	Pumps	4 do
Waterways	do	Transoms, Pointers, and Crutches	do	Boats	3 do
Comings	do	Timbers of the Frame	do	Masts, Yards, &c.	do
Upper Deck Beams & Fastenings	Round	Keelsons	do	Sails	do
Lower Deck Beams & Fastenings	8 Iron	Clamps and Shelves	do	Anchors	No. of 3 1/2 Bu 1 Stem 1 Kedge
Planksheers	good	Ceiling	do	Cables	Complete and Good
Sheerstrakes	do	Rudder	do	Hawsers and Warps	do do
Topsides	do	Supper	do	Standing & Running Rigging	do do
Wales	do	When put on	Aug 1855		
Plank (Bottom) and Counter	do				

General Observations and Opinion. *It is in good efficient Condition and fit for the safe
Conveyance of Dry and Perishable Cargoes to and from all parts of the
World and may continue as afloat*

The Amount of Fee.....£ 2 : 5 : 5 is received by me,

Special Damage 2 : 2 : 5

Certificate (if required) *h* : *h* : *h*

Committee's Minute *6th Sept. 1853*

Character assigned

A close-up photograph of a book cover. The cover is primarily blue with a large, white, stylized 'LR' logo. Overlaid on the 'R' is a black ink signature that appears to read 'C. J. ...'. The background of the cover features a faint, repeating pattern of the letters 'LR' in a lighter shade of blue.

© 2019

Lloyd's Register
Foundation

GLS141-0228