

1133

405
on the *Ship "John Gray,"* Master *Alexander Calder*

By whom built 5 Owners James Spier

If Surveyed Afloat or in Dry Dock Patent Ship

REPAIRS Shipped the Yellow Metal Sheathing, Cleaned the Bottom, Scraped bright from the Light Water Line to the Waterways included and drove out Deck and Hold Beam Bolts for inspection and Special Survey. Renewed the Fore piece of Keel and the Fore and After Length of Garboard Stake and Stake next on the Starboard Side and two Stanchy Unionships with American Elm New Ripe and False Stern Post and Rudder and part of False Keel forward, New Mizen Mast, Fore Mast topped at the keel, all new Ceiling in the After Peak on both sides from the Keelson 6' 4" Stakes American Elm, a number of Greenings and Beam Bolts renewed Caulked from Keel to Gunwale and Sheathed the Bottom with Yellow Metal over Paper below and Felt above Deck and Waterways Caulked last March.

<i>Present Condition of the</i>			
Decks	<i>Good</i>	Treenails	<i>Good</i>
Waterways	<i>do</i>	Breasthooks and Stemson	<i>do</i>
Comings	<i>do</i>	Transoms, Pointers, and Crutches	<i>do</i>
Upper Deck Beams & Fastenings	<i>do</i>	Timbers of the Frame	<i>When Seen do</i>
Lower Deck Beams & Fastenings	<i>do</i>	Keelsons	<i>do</i>
Planksheers	<i>do</i>	Clamps and Shelves	<i>do</i>
Sheerstrakes	<i>do</i>	Ceiling	<i>Some New do</i>
Topsides	<i>do</i>	Rudder	<i>New</i>
Wales	<i>do</i>	Sopper	<i>P. Mott When put on Oct. 55</i>
Plank (Bottom) and Counter	<i>do</i>	Windlass and Capstan	<i>Good</i>
		Pumps	<i>4 do</i>
		Boats	<i>3 do</i>
		Masts, Yards, &c.	<i>do</i>
		Sails	<i>do</i>
		Anchors No. of	<i>3 B. 1 Heavy 1 Midge</i>
		Cables	<i>Good</i>
		Hawsers and Warps	<i>do</i>
		Standing & Running Rigging	<i>do</i>

Caulking of Bottom, Deck, & Waterways. *New & Good*

*Especially Surveyed in Accordance with the Rules Section 54, 860.
 Is now in good and efficient Condition fit for the safe
 Conveyance of Dry and Perishable Cargoes to and from all parts
 of the World and we are of opinion that she may be Classed G*E.*

Oct 11
Special..... 44: 44: '3

Committee's Minute 10th October. 1855

~~A~~, ! asterisk

Record ^{D. S.} ~~Repair~~

Rich^d Robertson
John. Maxwell Junr.