

Report of Survey for Repairs of Engines and Boilers.

No. *57473*

(Received at London Office, *25/8/81*)

No. in Reg. Book. *390*

Survey held at *Glasgow*

Date, first Survey *Aug⁴th* Last Survey *Aug¹⁰th* 188*1*

on the Machinery of the

S.S. "Douglas"

(Number of Visits *3*)

Tonnage, Gross *101*

Built at *Port Glasgow*

When built *1876*

Ditto, Net *52*

Owners *H. Middleton*

Port belonging to *Glasgow*

Diameter of Cylinder *15" x 26"*

Engines made by *Muir & Houston*

When made *1876*

Length of Stroke *21"*

Boilers made by *"*

When made *1876*

Pressure of Steam *60 lb*

If Surveyed Afloat or in Dry Dock *on Slipway*

Classed *90 A.1.*

Registered Horse Power *30*

(State name of Dock.)

Years assigned. *90 A.1.*

Last Survey No.

Port

Particulars of Repairs and Examination of Machinery as per Rule for S.S. No. 1

(State cause of Repairs.)

The Vessel was placed on the slipway at this port. Propellers and outer end of shaft examined and found in good order.

Sea Cocks examined and found in good order.

The plating round main boiler blow-off cock was corroded a new plate was riveted on and the cock re-jointed. Crank shaft, Cylinder, Slides, Air Circulating, Feed, and Midge pumps examined and put in good order.

Main boiler opened up and examined. All plates and stay tubes runned. One riveted patch on front plate. Two small patches on bottoms of Combustion Chambers fitted. Bottoms seams of shell overhauled and caulked in places as required.

Spring Safety Valves overhauled and tested under steam and adjusted to 60 lb per sq inch working pressure and new brass rings fitted under compression nuts.

General Observations, Opinion, and Recommendation:— *The above machinery is now in good order and safe working condition and eligible in my opinion to remain as classed. Lloyd M.C. 8. 81. in the Society's Register Book.*

Entry or Registering Fee (per Section 27.) *£ - : 10 :*

Survey Fee (per Section 28) *£ 2 : 2 :* received by me, *J.M. Grogan*

Certificate (if required) *£ , : , : 25/8/81*

to be sent as per margin.

(Travelling Expenses, if any, £ *11* - - -)

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.

Committee's Minute

188

Assigned

J.M. Grogan
© 2019
Clyde District Register
Foundation

GLS 146-0060

54739
It is submitted that this vessel is
eligible to have the notification
stop to M.C. & S. records, subject
to the order being reassured
when six years old as
per rule

M 25/98



© 2019

Lloyd's Register
Foundation