

Report of Survey for Repairs of Engines and Boilers.

(Recd 20.3.77)

No.

No. in
Reg. Book. Survey held at

London

Date, first Survey

Last Survey

11th March 1877

23 on the

S.S. Cadiz

Master

Tons

1400

Owners

J. Hall & Co

Port belonging to

London

Classed

Years
assigned.

Character in Register Book.

100 A1

8.76

Diameter of Cylinder 8 24 x 4 1/2 2 of each

Length of Stroke

36

Engines made at

Newcastle

When made

1869

Pressure of Steam

45 lbs

Registered Horse Power

200

By whom made

J. R. Hawthorn

Particulars of Repairs and Examination

New Propeller, new after length of Propeller shaft.
And new stern bush. Stem tube bored out to suit
new stern bush which is six inches longer than the
one previously fitted. Slight crack in inner
surface of after high pressure cylinder, repaired
by fitting phosphor bronze chamber one half inch
thick in cylinder. Chamber sunk in its place and
secured with pins.

Examined boilers and found them in fair
condition.

It is respectfully submitted that the ship
is eligible to remain as classed in the Register Book

The Amount of Fee ... £ 1 : 1 : 0

Certificate (if required) ... £ :

received by me,

187

(Travelling Expenses, if any, £

Committee's Minute

11th October,

1878.

Engineer Surveyor to Lloyd's Register of British & Foreign Shipping.



© 2019

Lloyd's Register
Foundation

FROM 480-0345