

Continuation 13175 **REPORT of SURVEY for REPAIRS.**

No. 183 Survey held at London Date Feb¹⁴ 1847
 on the Sc² Agnes Master R. F. Ducken
 Tonnage 137 Built at Greenock When built 1830
 By whom built _____ Owners Alex^r Denniston & Co
 Port belonging to Liverpool Destined Voyage Antigua & Havana
 If Surveyed Afloat or in Dry Dock On New Crane Ways in London Dock

Last Survey, No. 7117 Classed of A 1
 Port Liverpool 45

REPAIRS at the present time in complying with Rule for Continuation Section N^o 54. The outside Planking from Copper upwards scraped bright. Bolts and Treennails driven out for examination at various parts, and all the Treennails from lower part of Wales upwards on each side renewed. a new lower Breast-Hook of Iron and through Bolts with Copper, 12 Sheets of Copper expended in Patching. Caulked from Copper upwards to second Seam of Deck next the Waterway.

Repairs of damage, Six Stantions, the whole of Bulwark, 40 Feet of Main Rail Starb^d and thirty Feet Larb^d are new

The Coamings, Deck Bolts, Planksheer, Waterway, Beams, Knees, Inside and outside Planking, Treennails, Haulse Timbers, Knight heads, Floors, Timbers of the Frame, Transoms & Breast Hooks where they may be seen have been examined by us and are in good condition. The Keel is straight and her original Form appears to be preserved unaltered.

Present Condition of the

Decks		Treennails new from lower edge of Wales upwards		Windlass and Capstan	
Waterways	} good	Breasthooks and Stenson		Pumps	
Comings		Transoms, Pointers, and Crutches	good where seen	Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame		Masts, Yards, &c.	} In good order and sufficient
Lower Deck Beams & Fastenings	} d ^o where seen	Keelsons	d ^o	Sails	
Planksheers		Clamps and Shelves	d ^o	Anchors No. of	
Sheerstrakes	d ^o	Ceiling	d ^o	Cables	
Topsides	d ^o	Rudder	d ^o	Hawsers and Warps	
Wales	d ^o	Copper	1045 d ^o	Standing & Running Rigging	
Plank (Bottom) and Counter	d ^o				

General Observations and Opinion,

This Schooner has now been 'Specially surveyed' by us in accordance with Rule for Continuation Section N^o 54 and we are of opinion that she is now in good condition fit to be continued A 1 for 3 years from 40

The Amount of Fee.....£ 2 : - : - is received by me. H

Certificate (if required) : 5 : - H

Committee's Minute 23rd Feby 1847

Character assigned Ant A 1

Special or Continuation £ 3.. 3.. 0 H



© 2019
 Lloyd's Register
 Foundation
 LON 622-0252