

ANNUAL SURVEYS.

15270

See July

No. 12 Survey held at London Date July 28th 1849
 on the "Baque" Nelson Master W. H. Lamond
 Tonnage 510 Built at Dumbarton When built 1844
 By whom built 603 Owners Potter & Co
 Port belonging to Glasgow Destined Voyage Port Philip
 If Surveyed Afloat or in Dry Dock In Green's Dry Dock

Last Survey, No. 1563 Port of Leith Classed 10 A 1
 47

The present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } good	Breasthooks and Stemson } good when seen	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. In good order
Lower Deck Beams & Fastenings } d ^o when seen	Keelsons part seen d ^o	Sails and sufficient
Planksheers	26 feet of the Keelson run in midship d ^o	Anchors No. of 3 1 1 2
Sheerstrakes d ^o	Clamps and Shelves d ^o	Cables
Topsides d ^o	Ceiling in Flat not seen d ^o	Hawsers and Warps
Wales d ^o	Rudder d ^o	Standing & Running Rigging
Plank (Bottom) and Counter d ^o	Copper Metal on When put on now new	

General Observations and Opinion,

Now done. The Yellow Metal Sheathing stripped off and renewed upon Felt aloft (5 bucastrs) and Paper below. Ship hung in thows, the Bottom, Waterway and two seams of Upper Deck next the Sides Caulked. 10 Iron Bolts of Lower Deck fastenings replaced with new, and a new dim

Committee Minute 10th July 1849 to one broken Beam of Lower Deck.
 Character assigned 10 A 1 The ship appears to be in good condition.
 record Ym Ship to remain Classed A 1
 J. S. Martin Certificate (if required)

No. 66 Survey held at London Date July 3rd 1849
 on the "Kirkman Finlay" Master J. Potter
 Tonnage 439 Built at Greenock When built 1834
 By whom built Owners Russel & Co
 Port belonging to Greenock Destined Voyage Ceylon
 If Surveyed Afloat or in Dry Dock In Messrs Young Son & Co Dry Dock

Last Survey, No. 1421 Port of London Classed 12 A 1
 Cont 46. 4. 40

The present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways } good	Breasthooks and Stemson } good when seen	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. In good order
Lower Deck Beams & Fastenings } d ^o when seen	Keelsons d ^o	Sails and sufficient
Planksheers	Clamps and Shelves d ^o	Anchors No. of 3 1 1 2
Sheerstrakes d ^o	Ceiling d ^o	Cables
Topsides d ^o	Rudder d ^o	Hawsers and Warps
Wales d ^o	Copper Metal on When put on now new	Standing & Running Rigging
Plank (Bottom) and Counter d ^o	upon Felt	

Now done. The Yellow Metal Sheathing stripped off and renewed upon Felt, a new Barrel to Windlass, and Pall Butt new, one Beam of Lower Deck repaired with a middle piece it being broken.
 Committee Minute 10th July 1849 The Bottom Caulked. The ship appears to be
 Character assigned Cont 46 in good condition eligible to remain Classed A 1
 record Ym Ship to remain Classed A 1
 J. S. Martin Certificate (if required)