

# REPORT of SURVEY for REPAIRS.

1797<sup>3</sup>

No. 1 Survey held at London Date Jan 7<sup>th</sup> to 17<sup>th</sup> 1853  
 on the By Diana Master  
 Tonnage 220 Built at Greenock When built 1837  
 By whom built 238 Owners Wm Sir John Foster & Co  
 Port belonging to Greenock London Destined Voyage Australia  
 If Surveyed Afloat or in Dry Dock Princes Dock  
Srprs 46 & 47

Last Survey, No. 2402 Port Clyde Classed 10 R. 1 Ship  
C 3 47 omitted

REPAIRS At the present time scraped bright & bolts & keennails driven out in various places for examination, an additional iron cutch aft, linster shakes through bolted with yellow Metal bolts, two new rough tree stations, one new plank of red pine on the topsides, two new planks in the drift of the quarter deck, the sheathing stripped off the wales & upper course of the bottom, yellow Metal stripped off the bottom, caulked, & re-sheathed with yellow Metal on paper, three new planks in the deck

The keennails & bolts are in good condition also the planks through which they pass, the plank sheers, waterways, beams, hawse timbers, knight heads, breasthooks, transoms, floors & keelsons are all in a sound state & appears to have preserved her original form

Present Condition of the		
Decks	Treenails	Windlass and Capstan <u>good</u>
Waterways	Breasthooks and Stemson	Pumps <u>Do</u>
Comings	Transoms, Pointers, and Crutches	Boats <u>Do</u>
Upper Deck Beams & Fastenings	Timbers of the Frame	Masts, Yards, &c. <u>Do</u>
Lower Deck Beams & Fastenings	Keelsons	Sails <u>Do &amp; well found</u>
Plank sheers	Clamps and Shells	Anchors No. of <u>3 Browsers &amp; 1 Redg</u>
Sheerstrakes	Ceiling	Cables <u>well found</u>
Topsides	Rudder	Hawsers and Warps <u>Do</u>
Wales	Copper	Standing & Running Rigging <u>good</u>
Plank (Bottom) and Counter	When put on <u>1853</u>	

General Observations and Opinion, This vessel has complied with the rule Section 61 & we are of opinion she is in a fit & good condition for the safe conveyance of dry & perishable cargoes to & from all parts of the world & may be classed A with the distinction of the Asterisk

The Amount of Fee.....£ 1 : - : - is received by me,  
 Special..... 3 : 3 : -  
 Certificate (if required) : :  
 Committee's Minute 18<sup>th</sup> Jan 1853  
 Character assigned A 1 1 Asterisk  
Wm Sir John Foster  
J. H. Hatcher  
 Lloyd's Register Foundation  
 LON 632-0431