

18/25

REPORT of SURVEY for REPAIRS.

No. 38/ Survey held at London Date 17th Feb 23rd Mar 1853
 on the Ship "Elizabeth" Master Robertson
 Tonnage 151 Built at Grunock When built 1836
 By whom built _____ Owners Cree & Co no change
 Port belonging to Grunock Destined Voyage Port Phillip
 If Surveged Afloat or in Dry Dock in Savender Dock & Afloat

Last Survey, No. 17, 223 Port London Classed 19 B

REPAIRS at Present Sheathing Stopped off the walke and the walke dyked bright, topsides and sheerstrakes scraped bright - the yellow metal sheathing stopped off, the Vapal Caulked from Kurl to gunwale and bottom Lashed with yellow metal new false Kurl fitted forward - the after lengths of sheerstrake removed timbers exposed sound & good - all the flat of the upper deck etc removed from the after lengths under the Poop forward and 5 additional upper deck beams fitted of English oak timber each secured with iron hanging knees say 5 inches New middle piece fitted in lower breast hook one length New Main Kelson 58 ft under Main Mast

Present Condition of the	length New Main Kelson 58 ft under Main Mast		
Decks	New except after lengths better	Treenails	Good
Waterways	Good	Breasthooks and Stemon	Good
Comings	5 new beams & 8 other timbers	Transoms, Pointers, and Crutches	Good
Upper Deck Beams & Fastenings	Keelsons	Timbers of the Frame	Good
Lower Deck Beams & Fastenings	Keelsons	Keelsons	Good
Plank sheers	Scraped	Clamps and Shells	Good
Sheerstrakes	bright	Ceiling	Good
Topsides	Scraped	Rudder	Good
Wales	Scraped	Copper	Good
Plank (Bottom) and Counter	Good	When put on	Mar 1853
		Windlass and Capstan	Good
		Pumps	New
		Boats	Good
		Masts, Yards, &c.	Sufficient
		Sails	Dr
		Anchors No. of	3, 1, 1
		Cables	Suff
		Hawsers and Warps	130
		Standing & Running Rigging	Dr

General Observations and Opinion,

This Vessel is now in efficient Condition and in our opinion fit for the safe conveyance of dry perishable Cargoes to & from all parts of the world and eligible to be classed with asterisk & 1 with marks S & 1853

The Amount of Fee.....£ 2 : : is received by me,

Special..... 3 : 3 : :

Certificate (if required) : 10 : :

Committee's Minute

Character assigned

Special L. 1 -

Lloyds Register
 Foundation

LON633-0064

18125 Son

and 48 feet new hog Keelson 5' deep - all new
^{flat} top gallant for castle deck laid - new Cutheads
new lead pumps with brass chambers - Hull
most rigging generally overhauled and refitted
the bolts and screws driven out for survey found
sound & good all the Regiments of Tubes Section
so Complied with and the Sheer and general
form appear unaltered -

J H Ritchie



© 2019

Lloyd's Register
Foundation