

REPORT of SURVEY for REPAIRS.

and change of Owners.

No. 203 on the *S. "Isabella Hercules"* Master *J. Sewell*
 Survey held at *London* Date *2nd to 23rd July 1855*
 Tonnage *534* Built at *Ardrossan* When built *1847*
 By whom built _____ Owners *Alexander & Co*
 Port belonging to *Workington* Destined Voyage *Australia*
 If Surveyed Afloat or in Dry Dock *Dowson's dry dock*

Last Survey, No. *18227* Port *London* Classed *13 A 1*

REPAIRS Now done: - On the starboard side, 5 first futlocks and 8 chocks, and on the Port side 3 first futlocks and 5 chocks renewed with English Oak. Three iron breasthooks upset, refitted, and rebolted with Yellow Metal. Lower piece of Apron and Stemson-knee new of English Oak. Hog keelson new Fore and aft, of E. S. Teak. All the fore hoods of ceiling on each side, from the lower deck clamp downwards, and also the fore hoods of Limber strakes renewed with English Oak, E. S. Teak, and African Oak. Treennails from Sheer strakes to Copper line renewed with Stringy Bark, and Blue-Gum. Yellow metal sheathing stripped off and renewed on tarred felt. Ship caulked from Copper line up, including the flat of the upper deck.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame <i>Good where</i>	Masts, Yards, &c. <i>Good and</i>
Lower Deck Beams & Fastenings <i>Good where</i>	Keelsons <i>seen</i>	Sails <i>sufficient</i>
Planksheers <i>seen</i>	Clamps and Shelves	Anchors No. of <i>3, 1, 1</i>
Sheerstrakes	Ceiling	Cables
Topsides	Rudder	Hawsers and Warps
Wales	Copper <i>YML & felt</i> When put on <i>new</i>	Standing & Running Rigging
Plank (Bottom) and Counter		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways *good*

The defects which occasioned the above-enumerated repairs, having been made good in a satisfactory manner, we are of opinion that this vessel is eligible to remain as classed.

The Amount of Fee.....£ 2 : - : - is received by me,

Special..... 2 : 2 : -

Certificate (if required) : 5 : -

Committee's Minute *7th August* 1855

Character assigned *13 A 1*

Record repair

Fee for Attendance £ 2 2 0



© 2019

Lloyd's Register Foundation

LON636-0128