

REPORT of SURVEY for REPAIRS.

No. 353 Survey held at London Date Feb 20th to Mar 3rd 1856
 on the Three Masted Sch^r Elizabeth Master Green
 Tonnage 105 Built at Brixham When built 1839
 By whom built _____ Owners Green & Co
 Port belonging to Brixham Destined Voyage Ancona & Trieste
 If Surveyed Afloat or in Dry Dock St Katherine's Dock

Last Survey, No. 1393 Port Dartmouth Classified Rest 53-7 A.I.

REPAIRS for damage from collision for particulars see the Special Report.
 All on the L^d side - one hawse timber, the upper part of the knight-head
 fourteen Raupstruts and timber heads, three planks in the sheer strake,
 three planks in the Topsides aft, the quarter timber, breasthook under
 the bowsprit, two head rails, the Taff rail, one hundred and twenty feet
 of Main bulwark, seventy feet of top gallant bulwark and thirty feet
 of Stern beamthing renewed. Caulked from the Black strake to the
 second seam on deck and the bow downwards in the wake of the
 new hawse timber. - The Bowsprit and jibboom new

Present Condition of the

Decks <u>part Caulked</u>	Treenails <u>good where seen</u>	Windlass and Capstan _____
Waterways <u>part Caulked</u>	Breasthooks and Stemson _____	Pumps _____
Comings <u>good</u>	Transoms, Pointers, and Crutches _____	Boats _____
Upper Deck Beams & Fastenings <u>part new</u>	Timbers of the Frame <u>Hold filled with Cargo</u>	Masts, Yards, &c. <u>Good and</u>
Lower Deck Beams & Fastenings <u>not run</u>	Keelsons _____	Sails <u>suft</u>
Planksheers <u>part Caulked</u>	Clamps and Shelves _____	Anchors No. of _____
Sheerstrakes <u>good</u>	Ceiling _____	Cables _____
Topsides _____	Rudder _____	Hawsers and Warps _____
Wales _____	Copper _____ When put on _____	Standing & Running Rigging _____
Plank (Bottom) and Counter _____		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good

She now appears fit in my opinion to remain as classed 7 A.I.
P. W. M. M. M.

The Amount of Fee.....£ — : 10 : — is received by me, [Signature]

Special.....: : :

Certificate (if required) : : :

Committee's Minute 11th April 1856

Character assigned Rest 7 A.I.

Damage paid £ 3. 3. 0

(Record damage repair)

[Signature]



© 2019

Lloyd's Register Foundation

LON636-0540