

REPORT of SURVEY for REPAIRS.

No. 183 on the S. "Isabella Mercus" Master H. Sewell J.M. Mitchell
Survey held at London Date 18th Apr^e to 9 May 1859
Tonnage 569 Built at Ardrossan When built 1847
By whom built Owners J. Holmes
Port belonging to London Destined Voyage East Indies
If Surveyed Afloat or in Dry Dock Lavender dry dock St Katherine's dock

May 12 5.59

Last Survey, No. 19033 Port London Classed 13A1

REPAIRS

Yellow metal stripped off. - Through worming - One piece of keel (20 ft long) now renewed with English Elm. 8 planks of bottom forward on the starboard bow new of American Elm and one after plank of Wales on the port side of East India Stair.
Through defects or decay - Rudder keelson (American Oak) removed, the defective sap of main keelson (Greenheart) cut out and a new Rudder keelson of Pitch Pine 15 x 10 ins wrought and iron bolted - 2 Stow Beams fore side of main hatchway scaphe with East India Stair.
recaulked from keel to upper edge of Wales and resheathed with Yellow metal on feet.
Through damage - 3 rough tree timbers of English Oak, one piece of bulwark Rail & part new bulwarks all on the port side
New lower masts, main & topgallant yards

Present Condition of the

Decks		Treenails		Windlass and Capstan	
Waterways		Breasthooks and Stemson		Pumps	In good
Comings	Good	Transoms, Pointers, and Crutches	Good	Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame		Masts, Yards, &c. ^{pt new}	
Lower Deck Beams & Fastenings	where	Keelsons ^{pt new}	where	Sails	order and
Plank sheers		Clamps and Shelves		Anchors No. of	
Sheerstrakes		Ceiling	seen	Cables	
Topsides		Rudder		Hawsers and Warps	
Wales	seen	Yellow metal on feet	When put on Apr/59	Standing & Running Rigging	Sufft
Plank (Bottom) and Counter ^{pt new}		Copper			

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good where tested

This vessel is now in good condition and eligible to continue as classed 13A1

Wm L. Davy
J. Martin

The Amount of Fee.....£ 2 : - : is received by me,

Special..... 2 : 2 : -

Certificate (if required) : 5 : -

Committee's Minute 17th May 1859

Character assigned 13A1

record repairs



© 2019

Lloyd's Register
FOLIO 641-0108