

# REPORT of SURVEY for REPAIRS, &c.

42793

No. in Survey held at London Date, first Survey Aug 17 Last Survey Aug 9<sup>th</sup> 1883  
 Reg. Book. 104 on the Iron Screw Steamer KENT. Master Drum  
 TONNAGE under Tonnage Deck 794 Built at Sunderland When built 1881  
 Ditto of Spar Deck, or Awning Deck 794 Owners Lambert Bros. Port belonging to London  
 Ditto of Poop \_\_\_\_\_  
 Ditto of Raised Qr. Dk. \_\_\_\_\_  
 Ditto of Houses on Deck \_\_\_\_\_  
 Ditto of Forecasts \_\_\_\_\_  
 Gross Tonnage 1045 Residence \_\_\_\_\_  
 Crew Space, as per Rule \_\_\_\_\_ By whom built D. F. Austin & Co. Destined Voyage Cardiff.  
 Register Tonnage cut on Beam \_\_\_\_\_ If Surveyed Afloat or in Dry Dock Union Dry Dock  
 Engine Room \_\_\_\_\_ (State Name of Dock)  
 Reg. Tons as St' mer, cut on Bm. 665

Length of Poop 23 ft. Ditto, Forecastle, 19 ft. Ditto, Raised Quarter Deck 55 ft.  
 Last Survey, No. 13284 Port Std Classed 100.A.1.  
~~12984~~ Std 1-83

REPAIRS, OR EXAMINATION AS PER RULE Cause of Repairs to be clearly stated. Damage Repairs.  
 State dates of any letters respecting this case \_\_\_\_\_ Society's Freeboard (if assigned) as painted on Ship \_\_\_\_\_

Two new plates to lower portion of Quader, and connected to the upper, and to each other by a solid forged butt strap. One plate taken off fared and replaced in the 3<sup>rd</sup> Strake below sheer stake amidships on the Starboard side. One broken and butt plate taken off the upper strake on the Port quarter, and renewed. The upper mouldings replaced and the circular side light refitted. Handrails staunches on Starboard & Port side of Raised Quarter Deck repaired, new work painted also Topsides & bottom.

Present Condition of the Decks	good	Keelsons	good	Windlass and Capstan	good
Waterways	"	Clamps and Shelves	good	Pumps	6
Comings	"	Ceiling	good	Boats	3
Upper Deck Beams & Fastenings	"	Rudder	repaired 2 new plates good	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Copper (or Y.M.)	When put on	Condition, how ascertained	from deck
Planksheers	"	Cement (if Iron Ship)	1881	Sails	2 Sails good
Sheerstrakes	"	Caulking of Bottom, Deck, & Waterways	good	Anchor	No. of 3 B-18-21G.
Topsides	"	Engine Room Skylights	good	Cables	good what seen
Wales	"	Coal Bunker, Openings, Lids, &c.	good	Hawsers and Warps	9 good
Plank (Bottom) and Counter	"	Scuppers	good	Standing & Running Rigging	good
Engine Room Skylights	good	Cargo and Main Hatchways	good	Hatches	good

This vessel has been placed in dry dock the bottom examined, scraped and painted. & she appears in sound and efficient condition and eligible in my opinion to remain as classed

The Amount of Entry Fee ... £ : : received by me, apth  
4/9/83 Special ... £ 2-2-0 14/9 1883  
 Certificate (if required) to be sent as per margin... } £ : :  
 (Travelling Expenses, if any, £ \_\_\_\_\_)  
 Committee's Minute  
 Character assigned 100.A.1.

Edward J. Tierney  
 Surveyor to Lloyd's Register of British and Foreign Shipping.

4 SEPTEMBER 1883



© 2021  
 Lloyd's Register  
 Foundation

(If a ... is also sent on the Machinery ...)  
 (The Surveyors are requested not to write on or below the space for Committee's Minute.)  
 (Form No. 2 for ... 40-7/83.)

(Insert Character precisely as in Register Book.)

LON 671-0036