

60810<sup>9</sup>. Lon.SURVEYOR'S REPORT.  
on Screw Steam Schooner Altata

Captain  
Tons  
Dimensions  
When and where built  
Builders  
Owners  
Hails from  
Material  
When metaled  
Topsides when calked  
Decks do.  
Cables  
Anchors  
Rigging  
Spars  
Sails  
Running gear  
Boats  
Hawsers  
Lines  
Tarpaulins  
Steering gear  
Rate  
Freeboard  
Draft of Water

Joaquin Alano  
78 94/100  
Length, 101 ft. 4 in. Breadth, 17 ft. 1 in. Depth, 9 ft. 3 in.  
1881 Deptford Kent England  
W. Walker & Co. Deptford Kent  
Occidental Mexican Company  
Altata Sinaloa Mexico  
Iron and Steel keel plates 1/2 in

Last year  
2, 90 faths. each 8 in diam. of link  
16 Bowers 1 Steam. 2 kedges, 16 fore Bower  
Wire rope good  
All spars good condition  
1 Storm trysail 1 Staysail 1. jib. middling  
in good. order  
3 boats in good condition  
2 Hawsers one 120 faths 6 in. 1. 100 faths 6 in.  
4 lines 100 faths. each good condition  
2 Fore hatch 2 After hatch  
in good condition  
Last rate A. 1.  
2 ft. 6 in.  
8 ft. 0 in. E. K.

## REMARKS.

The above vessel was hauled up on the ways, in the Port of Guaymas on the 2<sup>nd</sup> of February 1899, and steel keel plates were put on to my satisfaction, and also the bottom of the vessel was completely cleaned and three coats of patent paint laid on; also the madder gudgeons were fixed, also raised the shaft to line, and new Lignum vitae bearings, also overhauled the boiler and put in several staybolts, and to my judgement I consider that the Steamer Altata is in good condition for many years to come, both to Machinery and Hull of the vessel.

The vessel was also well cemented inside with Portland cement.

Surveyed at ~~Guaymas~~ Guaymas Feb 26<sup>th</sup> 1899  
By request of Lloyd's Agent  
at Maratlán.

J. J. Alexandre  
PILOT OF H. B. M. SHIPS ON THIS COAST.

I, E. Philipp, substitute of the Consul of the German Empire at Maratlán do hereby certify that the above is the genuine signature of Mr. J. J. Alexandre, Pilot of H. B. M. Ships on the coast of Mexico and was given before me. In witness whereof I put my hand and seal.



Maratlán, March 6<sup>th</sup> 1899  
The Consul of the German Empire  
E. Philipp

Lloyd's Register  
Foundation