

ENCLOSURE.

Communication on this subject  
should be addressed to  
THE SECRETARY.  
and the following Initial should be  
quoted in the left-hand corner

P

# Lloyd's Register of British and Foreign Shipping.

2. White Lion Court, Cornhill, E.C.

1st., January, 1895.

Dear Sirs,

I am in receipt of your letter  
of the 31st, ultimo submitting for the Committee's approval, the  
tracing of the steel boiler proposed to be made by your-  
selves for the s.s. "ELSY",

, and in regard thereto I am  
directed to acquaint you that the boiler in question will be approved of  
for the intended working pressure of 90 pounds per square inch, provided

a  $\frac{1}{2}$ " doubling plate be fitted on the front tube plate as  
shewn amended on the plan: the stay tubes have each an effective  
area of not less than 1.56 sq. inches: the girders on the combus-  
tion chamber tops be made with  $\frac{1}{2}$ " plates, doubled: the top corner  
screwed stays in the boiler back plate next the centre wide water  
space have each an effective area of not less than 1.19 sq. ins., and  
the other marginal screwed stays marked O have each an effective  
area of not less than .91 sq. in.: two additional screwed stays be  
fitted in the boiler back plate where shewn ~~in-red~~ amended: the  
two rows of screwed stays in the boiler back plate, next the centre  
wide water space be pitched not more than 12" apart: the plan in  
other respects be adhered to, and the boiler be built under the  
usual conditions of survey and testing and to the entire satisfac-  
tion of the Society's local Surveyor.

The plan sent is returned herewith. etc.

Messrs S. Hodge & Sons

Millwall, E.

I am, Dear Sirs,

Etc.

Lloyd's Register  
Foundation

LON 728-0058