

Sp/2 Albertville

Received at Middlesbro Office. 28<sup>th</sup> April 1898

Lloyd's Register of British and Foreign Shipping.

(Report on Vessel No. 2406 Port Mdb)

No. SHIP ~~FORGINGS OR~~ CASTINGS.

The words FORGINGS or CASTINGS, IRON or STEEL, should be struck out as may be required.

I have to report that the undermentioned Iron or Steel Forgings or Castings, manufactured by Messrs. William Jessop & Sons Limited of Sheffield for the Vessel No. 449, being built by Messrs Raylton Dixon of Middlesbro have been inspected by me as set forth below, and found to be, so far as can be seen, Sound.

Rudder head "Quadrant."

Mark on Forgings.

Lloyd's No. 1682 1.4.98 2.9.98

Leonard Hallcross

Quadrant Sheffield 23/4/98

	STERN FRAME.	RUDDER FRAME.	STEM.
Material*		Siemens-Martin	
How made		Cast Steel	
Dimensions		5'-6" Rad bore 8 3/8" dia	
Progress on Inspection		Cast & finished	
Date when Inspected		11.10.97 20.11.97 1.4.98.	

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS, OR PARTICULARS OF TESTS APPLIED TO CASTINGS.

(A1935-2) Tensile 26.3 tons. Elongation 34% in 2"

Bend. 105° hot Broken

Drop test 7'-0" good.

Fee (if any chargeable) £

To be paid at Sheffield



© 2020

Lloyd's Register Foundation