

7, 1935,

(Freeboards assigned under the provisions of the U. S. A. Load Line Act of March 2, 1929 and/or the Coastwise Load Line Act of August 27, 1935).

When received in New York Office.....

ne of Vessel . . . "WINDING GULF" . . .

Official No. 216767 No. in Reg. Book 86472

t of Registry **Boston** State whether classed by Lloyd's Register **Yes**

ne of Owners **Koppers Coal Company** Date of Verification **30th June, 1939**
(Mystic Steamship Company)

I have to report that the freeboard from the centre of disc to the top of the deck, and the lines in connection therewith, as given below, assigned by the American Committee to this vessel, have been correctly marked on the vessel's sides, in accordance with the printed instructions and that all the conditions of assignment have been complied with:—

	Freeboard from Deck line	Load line
Summer in Tropical Seas (T)	6 ft. 8½ ins.	(a) 6½ ins. above centre of disc
Summer (S)	7 ft. 3½ ins.	(b) Upper edge of line through centre of disc.
Winter (W)	7 ft. 10½ ins.	(c) 6½ ins. below centre of disc
Winter North Atlantic (WNA)	7 ft. 11 ins.	(d) 7½ ins. below centre of disc
Load line for fresh water for Summer and Tropical Summer (F and TF) above top respective lines	7½ ins.	

the top of the deck line is set off in relation to the top of the $\left\{ \begin{array}{c} \text{steel} \\ \text{axle stand} \end{array} \right\}$ $\left\{ \begin{array}{c} \text{upper} \\ \text{chassis} \end{array} \right\}$ deck.

Timber Load Lines (where Applicable)

	Freeboard from Deck line	Load line	
Summer in Tropical Seas (LT)ft.ins.ins.	above LS
Summer (LS)ft.ins.ins.	above LS
Winter (LW)ft.ins.ins.	{ above } { below } LS
Winter North Atlantic (LWNA)ft.ins.ins.	below LS
Load line for fresh water for summer and Tropical summer (LF and LTF) above top			
respective linesins.		

Surveyor to Lloyds Register of Shipping.

Port No. 26038 Date of Assignment 30-6-39

Particulars for Record in Register Book.	{	Moulded Depth	34 ft.	5 ins.
		Freeboard	4 ft.	3 1/2 ins.
		Corresponding Draught	27 ft.	4 3/4 ins.

ed for Posting

34 ft. 5 ins.
2 ft. 3 1/2 ins.
27 ft. 4 3/4 ins.

Lloyd's Register
Foundation
w1002-0040