

SCREW STEAMER YARD No.1354, proposed to be built  
by Messrs. Harland & Wolff Ltd., Belfast.

-----  
Owners:- Messrs. Royal Mail Lines Ltd.

Rule Dimensions:- *540' x 73' x 45' to Upper dk. 53.5' to Bridge dk.*  
D = 43.3 23380 62800

Scantling Nos:

Proportions:- Length = 12 depths to Shelter Deck.  
10.09 depths to Bridge Deck.

-----  
Plans of Midship Section and Framing Profile submitted  
by the Belfast Surveyors.

The vessel has five complete decks and a combined  
forecastle and bridge and the draught desired 28'-8" moulded all  
seasons, is less than that which could be assigned as a complete  
superstructure vessel.

The vessel is insulated and chilled meat is to be  
carried in the hold and in the lower and orlop tween decks.

In view of the urgency expressed by the Builders, the  
keel and centre girder have already been approved by wire.

IT IS SUBMITTED that provided

#### COMPLIANCE


the vessel will be eligible to be classed 100A1 with freeboard  
corresponding to a moulded draught of 28'-8" all seasons. As  
this draught is less than that which could be assigned as a  
Complete Superstructure Vessel, the scantlings have been adjusted  
accordingly and in accordance with Section 2 Para.1 (e), the  
Builders should obtain the written consent of the Owners.

*as well as at the lower and orlop decks,*  
*main* ~~lower~~ deck, raised by the Builders, this could be approved in this  
case except in way of the panting area.

27.7.46

Copy to Freeboard Department.

ltrs 20 and 22.7.46  
ans 29.7.46  
4 plans, 2 retained.



Act © 2020  
9.8  
Lloyd's Register  
Foundation

W1012-0155