

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey

Date of Survey 14. 7. 32.

Name of Surveyor

Ship's Name. "Pinhel."  
 Port of Registry and Nationality. Lisbon Portuguese  
 Official Number. 136072  
 Gross Tonnage. 3204.16  
 Date of Build. 1915  
 Particulars of Classification. +100 A1.  
 Number in Register Book

Registered Dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
	335.5	48.1	23.30	2927.85
Length on LOADLINE.	335.0	Frame Depth 10 Rule " 5 1/2 "	Ceiling Fitted Sheer + .77	Peak } in above Tanks }
		2. 4 1/2 "	Drop in Tank = 2" / 2 = +.08	Below Line of Tank Top in BR
		- .75	Ordinary Floors in BR = .83	- 5.42
LECTED DIMENSIONS.	335.0	47.35	23.32	2922.43

Moulded Depth as measured..... 24'-10"

Addition for Keel below base line for draught record.....inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

## CORRECTION FOR LENGTH.

Length of Ship on Loadline.....	335.0
Length in Table .....	298.0
Difference .....	37.0
Correction for 10ft., Table A. ....	1.3
× Difference divided by 10 .....	4.81
If 1/10ths length covered divide by 2 .....	2.4
	+ 2 1/2

## CORRECTION FOR IRON DECK.

Proportion covered, if less than 1/10ths length covered .....	1
Thickness of usual wood deck, less stringer .....	3 1/2
	- 3 1/2

## CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships.....	46'-0"
Round of Beam .....	1'-0"
Normal round.....	11 1/2"
Difference .....	1/2" ÷ 2 = 1/4"
Proportion of Deck uncovered (Para. 19) .....	✓

NOTE.—The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A .....	5-6
Correction for Sheer .....	- 7
	4-11
Correction for Length .....	+ 2 1/2
	5-11 1/2
Allowance for Deck Erections .....	- 1-11 1/4
	3-2 1/4
Correction for Round of Beam.....	✓
Correction for fall in Sheer (if any).....	✓
Correction for Steel Deck (if required) .....	- 3 1/2
	2-10 3/4
Additions for non-compliance with provisions of Para. 11 (d) and (e) † .....	✓
Other Corrections (if any) .....	✓

Winter Freeboard .....	2'-10 3/4"
Summer Freeboard .....	2'-6"
Indian Summer Freeboard .....	2'-1 1/4"
N.A. Winter Freeboard .....	✓

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side. NIL

Winter Freeboard from deck line .....	✓
Summer " " " " .....	✓
Indian Summer " " " " .....	✓
N.A. Winter " " " " .....	✓

## SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:— 2'-5 3/4" = .756 m.

Tropical Fresh Water Line above Centre of Disc .....	10.79" = .274 m	Tropical Fresh Water Freeboard .....	492 m
Fresh Water Line .....	6.29" = .160 m	Fresh Water .....	596 m
Tropical Line .....	4.50" = .114 m	Tropical .....	642 m
Winter Line below .....	5.00" = .127 m	Winter .....	883 m
Winter North Atlantic Line .....	✓	Winter North Atlantic .....	✓

27 JAN 1933

1m, 0.32.

1.0 = 8030  
40 × 31.92

1.0 = 8030  
40 × 31.92

1.0 = 8030  
40 × 31.92

1.0 = 8030  
40 × 31.92

1.0 = 8030  
40 × 31.92

1.0 = 8030  
40 × 31.92

1.0 = 8030  
40 × 31.92

1.0 = 8030  
40 × 31.92

1.0 = 8030  
40 × 31.92

1.0 = 8030  
40 × 31.92

1.0 = 8030  
40 × 31.92