

= Survey held with Registro Italiano =

For the information of Surveyors and the Committee only.

apt. 7.

Order N°881/4 =  
of the 28th/5/24 =

Received at \_\_\_\_\_ Office, \_\_\_\_\_ 19\_\_

# Lloyd's Register of Shipping.

(Report on Machinery, No. 6987 Port Trieste)

No. 20 = ENGINE FORGINGS ~~OR CASTINGS~~

I have to report that the ~~Iron~~ Steel Forgings ~~or Castings~~, as herein described, manufactured by "TERNI" Soc: per l'Ind: & l'Elett: of Terni for the Engines No. = being constructed by Stabil: Tecnico Triestino of Trieste for the Ship No 138&744, being built by Stabilimento Tecnico Triestino of Trieste = have been inspected by me as set forth below, and found to be, so far as can be seen, sound & free from apparent defects =



*Antonio*

ck on Forgings or Castings.

Lloyd's No. <u>113</u> A. G. 20. 12. 24	LLOYD'S N°114 A. G. 20. 12. 24	LLOYD'S N°115 A. G. 20. 12. 24	LLOYD'S N°116 A. G. 20. 12. 24	Leghorn 20th/3/25
-----------------------------------------------	--------------------------------------	--------------------------------------	--------------------------------------	-------------------

	CROSS HEAD PIN-(N°113) <u>5023</u>	CROSS HEAD PIN-(N°114) <u>5023</u>	CROSS HEAD PIN-(N°115) <u>5023</u>	CROSS HEAD PIN-(N°116) <u>5023</u>
Material	S.M. Ingot steel	S.M. Ingot steel	S.M. Ingot steel	S.M. Ingot steel
How made	Forging	Forging	Forging	Forging
Dimensions	As under	As under	As under	As under
Progress on Inspection	Rough finished	Rough finished	Rough finished	Rough finished
Tests on Standard Test Pieces.				
Tensile Test— Tons per square inch	<u>48,3</u>	<u>48,3</u>	<u>47,6</u>	<u>48,2</u>
Elongation per cent	<u>17</u>	<u>23</u>	<u>18,4</u>	<u>24</u>
180° Bending Test— Angle before fracture	<u>180° good</u>	<u>180° good</u>	<u>180° good</u>	<u>180° good</u>
Dates when Inspected	<u>5/11&amp;20/12/24 =</u>	<u>5/11&amp;20/12/24 =</u>	<u>5/11&amp;20/12/24 =</u>	<u>5/11&amp;20/12/24 =</u>


PARTICULARS OF OTHER TESTS APPLIED TO CASTINGS:—

Sketch N°6/282 = (Weight of each cross head pin)  
Kgs: 446,7  
(See Report N° 17)

Fee (if any chargeable) £ 0 : 15 : 3 = Exp: 0 : 8 : 5 =  
To be paid at Leghorn =

\* If of iron, state whether scrap or puddled iron. If of steel, state whether made on the Open Hearth process.

19. T.



Assigned