

5/3/28

When landed at Local Office 5/3/28

Port of

Received at London Office GENOA

10 MAR 1927

COPY.

# Lloyd's Register of Shipping.



## RESULTS OF TESTS OF STEEL.

Port of GENOA

June 21st 1926

Serial No.	Thickness	Length	Area	Total Tons	Extension
1445	7.7	30.1	254	11800	46.6
1471	8.4				29.7

This is to Certify that

A. S. M A N T E L L I

the undersigned Surveyor to this Society did at the request of Messrs STABILIMENTI DI DALMINE of Dalmine, attend on 2/3/26 and subsequent dates at their Works at Dalmine, for the purpose of examining and testing No.8 (EIGHT) Steel Seamless Air receivers of the following dimensions:-

Ø 316 x 291 x 3200 (190 litres capacity)

intended for Messrs Società Anonima FIAT of Turin.-

Test pieces were selected out of the seamless tubes and the tubes themselves were carefully gauged for thickness and concentricity before the ends were closed in. A copy of the tensile tests' results is appended.

The air receivers were subsequently tested by hydraulic pressure to 160 Kgs. and during and after test were carefully inspected and found to be, as far as could be seen, sound and free from defects.

The air receivers were marked as follows:-

L L O Y D ' S   T E S T

No.10 - 65 ÷ 71

160 Kgs.

W. P. 80 Kgs.

A.S.M. 17-6-26

(Sgd) A. S. Mantelli

Surveyor to Lloyd's Register

*68, 71 fitted on board the SALTCELLINA*

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-  
 While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society.

10m.7.27.

