

m/v. May Glen

(ex Ottawa May Glen)

QUEBEC, Que.

16th October, 1946.

Steam Feed Pumps  
 2½" x 3½" x 5"  
 G & J Weir Ltd.,  
 Glasgow -  
Nos. 199683 & 199684

D. HALKETT

Messrs. PEACOCK BROTHERS LIMITED, MONTREAL, Que., attend on board the Steel Single Screw Motor Vessel "Ottawa May Glen", whilst in the outfitting yard of St. Lawrence Hotel and Marine Works Incorporated, Quebec, Que., for the purpose of witnessing a running test of PUMP PUMPS supplied by G & J Weir Limited, Cathcart, Glasgow.

The PUMPS were connected to the shore steam line, 100 lbs. pressure and maintained a steady hydraulic pressure of 165 lbs. on the boiler for a period of 30 minutes.

The CYLINDERS and PUMPS, as stated on the G & J Weir test sheet, had been subjected to a hydraulic test pressure of 400 lbs. per square inch prior to leaving their plant at Cathcart, Glasgow.

The materials and workmanship, so far as now seen, are good and sound and free from surface defects.

For identification purposes the PUMPS have been stamped:-

PUMP No. 199683

LLOYD'S  
 7778-A  
 D.H. 13-10-46

PUMP No. 199684

LLOYD'S  
 7778-B  
 D.H. 13-10-46

Int. Rpt. 6987

D. Halkett

SURVEYOR TO LLOYD'S REGISTER..



© 2021

Lloyd's Register  
 Foundation