

2 plans under separate cover.

Lloyd's Register of Shipping.

3, Steinhoeft,

Hamburg, 11th March, 1937.



RECEIVED
13 MAR 1937
ARR. 19.3.
LONDON

Reference

Dear Sir,

I am submitting under separate cover for the approval of the Committee duplicate copies of plan of "Ice strengthening" proposed for Messrs. Lübecker Maschinenbau Gesellschaft's Yard N 367.

The Builders point out that the butts of the shell plating are arranged to comply with the requirements of Table 39 of the Rules using the normal end thickness of 10 mm and accordingly double riveted butts are proposed with a diameter of rivet in way of the ice strengthening of 22 mm. In view of the width of flange rivets of 19 mm are proposed to be fitted in the frames in way of the ice strengthening forward and abaft the collision bulkhead. The lowest ice stringer is not extended beyond frame 124 on account of the stringer coming too close to the top of the tank side brackets.

I am, Dear Sir,
Yours faithfully

A. Christensen

The Secretary,

LONDON



© 2020

Lloyd's Register
Foundation

W1183-0257

