

G.R. 130.


CLASS CONTEMPLATED

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any)



Official Number.	Name of Ship.	No., Date, and Port of Registry.	
166331	POZARICA	1 in 1938 London	
No., Date, and Port of previous Registry (if any).			
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.
British	Motor Ship Single Screw	Sunderland	1938
Name and Address of Builders.			
Wm. Doxford & Sons Ltd., Sunderland.			
Number of Decks	One and Shelter Deck	Length from fore part of stem, to the aft side of the head of the stern post	Feet. 295 Tenths. 6
Number of Masts	Two	Main breadth to outside of plank	45 0
Rigged	Not	Depth in hold from tonnage deck to ceiling amidships	13 9
Stem	Straight	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards	- -
Stern	Cruiser	Depth from top of deck at side amidships to bottom of keel	17 7.4
Build	Clencher	Round of beam	- 9.4
Framework and description of vessel	Steel : Cargo	Length of engine room, if any	55 2
Number of Bulkheads	Watertight - Five		

Particulars of propelling Engines, etc., (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Estimated Speed of Ship.
One	Internal Combustion, Opposed Piston Type Vertical.	British	1938	Wm. Doxford & Sons Ltd., Sunderland.	Five 560 M/M	Upper Piston 700 M/M Lower Piston 980 M/M	-	734 3400 3860
No. of Shafts.	Particulars of Boilers.							
One	Description Auxiliary Number Two Iron or Steel Steel Loaded Pressure 120 lbs.	British	1938	Stockton Chemical Engineers & Riley Boilers Ltd., Stockton.	(22")	Total 1680 M/M (66 1/8")		15 knots

Number of water ballast tanks, and their capacity in tons:— Six - 364 tons.

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	1236.82	On account of space required for propelling power	840.86
Houses in Shelter	67.31	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind, not being the personal property of the Crew	150.77
Space or spaces between Decks	3.70		
Turret or Trunk Break	49.94		
Forecastle	169.06		
Bridge spaces (Upper Passenger)	72.68		
Poop or Break	55.18		
Side Houses	9.64		
Deck Houses	71.96		
Chart House			
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	152.72		
Excess of Hatchways			
Gross Tonnage	1893.01		
Deductions, as per contra	1054.98		
Register Tonnage	838.03		
		Cubic Metres.	
		5357.22	
		2985.60	
		2371.62	
		Masters' Accommodation 16.51	
		Chart Space 7.20	
		Wireless Telegraphy Space 4.85	63.35
		Boatswains Storeroom 11.09	
		Water Ballast Spaces 23.70	1054.98

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 327.77 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 152.90 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

(Part I Length 220.8 feet = 592.97 tons.

Shelter Tween Decks (

(Part II Length 4.2 feet = 12.10 tons.

Name of Master Percy Edwin Gould

Certificate of { Service No. 007884
Competency No.

No. of Owners


Name, Residence, and Description of Managing Owner if there are more owners than one.

MacAndrews & Co. Limited, 19, Leadenhall Street, London, E.C.3.


Shares - Sixty-four.

Dated 1st January, 1938.

Manager: Richard Lee Curphey of same address.



Lloyd's Register Foundation



© 2021

Lloyd's Register
Foundation

SPEC

Am

Particulars
Cast, Stee
Weight,
Number
of Test.

PARTICL

(in f

No. and Ma

Official

Particulars o

PARTICL

Double bottom,
Double bottom,
Double bottom,
Double bottom,
Double bottom,

Order for Special

Date

Ms. Soden