

NO RESPONSIBILITY WILL BE ACKNOWLEDGED FOR ANY CONSEQUENCES ARISING OUT OF STRIKES, COMBINATIONS OR OTHER LABOUR DISTURBANCES.
OFFERS FOR DRY DOCKING ARE SUBJECT TO DOCK BEING AT LIBERTY. ALL TRANSPORTING AT OWNERS' RISK.

R. & H. GREEN AND SILLEY WEIR LIMITED.

SHIP AND ENGINE REPAIRERS, BOILER MAKERS, ELECTRICAL ENGINEERS, IRON & BRASS FOUNDERS.

TELEPHONE NUMBERS:
GENERAL OFFICES: ALBERT DOCK 2121 (5 LINES).

TELEGRAMS: "REPAIRS, ALDOCK, LONDON."



Works:

BLACKWALL YARD: — EAST 4171 & 4172. SURREY DOCKS: BERNONDOSEY 3187 & 3188.
ROYAL ALBERT DOCK: ALBERT DOCK 1641 (13 LINES). MILLWALL DOCK: — EAST 4611 & 4612.
CENTRAL WORKS, ROYAL ALBERT DOCK: ALBERT DOCK 1506. TILBURY DOCK: — TILBURY 53 & 113.

CITY OFFICE: 130-132, LEADENHALL STREET, E.C.3.
TELEPHONE: AVENUE 8308 (3 LINES). TELEGRAMS: INTERKNIT, STOCK, LONDON.

BLACKWALL YARD,

LONDON, E.14

June 22nd. 1931.

DOCKS REGULATIONS, 1925.

Test Certificate No. 1889.

REGULATION 19 (a).

S.T. "KEVERNE"

Form prescribed by the Secretary of State for Certificate of Test and Examination of
Lifting Gear, namely:—Chains, Rings, Hooks, Shackles and Swivels.

Distinguishing mark. (1)	Description of gear. (2)	Number tested. (3)	*Proof load applied. (4)	Date proof load applied. (5)	Safe working load. (6)
G.			t. c. q.		t. c. q.
15617/19.	Steering chains, 5/8" chain.	3.	4.12. 0.	18-6-31.	2. 6. 0.
15620.	5/8" D shackle 5/8" hex head screw.	1.	1.14. 0.	do.	0.17. 0.
15621.	5/8" D shackle 5/8" square head screw.	1.	do.	do.	do.
15622/23.	5/8" D shackles 5/8" bolts and nuts.	2.	do.	do.	do.
15624/25.	5/8" D shackles 3/4" square head screws.	2.	2.14. 0.	do.	1. 7. 0.

1-1. Peak King

For and on behalf of
R. & H. Green and Silley Weir Limited.
Managing Director

(7) Was the gear examined by a competent person after the application of the proof load and found to have withstood the load without deformation and to be free from cracks, flaws or other defects?

Yes.

(8) Name and address of makers or suppliers.

Unknown.

(9) Name and address of firm or person making the test and examination (see (4), (5) and (7) above).

R. & H. Green and Silley Weir, Ltd.
Blackwall Yard, E.14.

I hereby certify, on behalf of the persons named in (8) above, that the above particulars are correct.

Signature

Date June 22nd. 1931.

*Chains of diameter not exceeding 1 1/2 in., Rings, Hooks, Shackles and Swivels must be subjected to a proof load equal to twice the safe working load, and other chains to a proof load equal to 1 1/2 times the safe working load.

W1208-0257

General