

S.T. "KEVERNE"

June 22nd. 1931.

PARTICULARS OF STEERING GEAR.

Port aft chain - 21'9" long, standard 5/8" chain.

Stbd aft chain - 22'5" " " " "

Gipsy chain - 44'0" overall, length centre of chain 18'10";  
special pitch chain, length of link  $3\frac{1}{2}$ " x  $2\frac{1}{8}$ " x  $\frac{5}{8}$ "; each end  
of chain 14'7" of  $\frac{5}{8}$ " standard chain.

Four  $\frac{5}{8}$ " D shackles with  $\frac{5}{8}$ " screw pins.

Two 1" stretching screws.

Two buffer springs  $4\frac{1}{2}$ " outside diameter  $\frac{13}{16}$ " square section,  
1'6" long, 15 coils.

Four rods with double joints each end.

Port aft - one rod 15'3" Forward rod 24'5".

Stbd aft - one rod 15'3" Forward rod 24'9".

*From Records.  
Rechecked by C. H. H.*



© 2021

Lloyd's Register  
Foundation

W1208-0258

W1208-0260 1/2