

COPY.

# Lloyd's Register of Shipping.



Port of MALTA

7th June 1930

This is to Certify that

Lewis J. Calcaterra,

the undersigned Surveyor to this Society did at the request of Captain D.J. Munro of the British Tug "JAUNTY" and Messrs. Cory Bros. Ltd., Owners' Representatives, complete the survey recently held at Plymouth for re-instatement of her class.

The bunker spaces were cleared for survey, oxidation removed from all parts and the steelwork carefully examined and found in good condition and afterwards recoated. The inner surface of the bottom plating is coated with cement and has been tested by beating and found sound and adhering to the steel.

The ceiling in way of bunkers has been lifted and the feed water tank under the after cross bunker tested as required by the Rules. Fourteen rivets in tank top plating were found defective and renewed, and minor leaks in laps of plating caulked.

*L. J. Calcaterra*

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society."