

Messrs. Hull & Chicken.

Second Hand Boiler ex Steam Drifter "WEST ANGLIA".

For S.S. "SPEY", No. 64277 in the Register Book.

IT IS SUBMITTED ~~that~~ the Sunderland Surveyors be informed that the actual scantlings of this second hand boiler, as shown on the plan, are such as could be accepted for a working pressure of 140 lbs/ins² provided four additional stay tubes be fitted as indicated on the plan.

approximate It is noted that the thickness of the plain tubes is *mentioned on the plan* slightly less than required by the Rules, and the Surveyors should therefore be requested to pay special attention to these when the boiler is tested by hydraulic pressure.

It is also noted that the boiler has been examined internally and externally and found in good condition.

Return tracing - print
Retain 1 print.

W.H.

W.H.

J.H. 20.9.38.

Lr 22/9



© 2019

Lloyd's Register
Foundation

W123-0248