

"Harvest Queen".

Nov. 77055.

Dis. 10760.

Ges. 39058.

Before this case receives consideration it is submitted  
the Report be returned to the Nvr. Surveyors & that  
be requested to fill in the required particulars  
arding safety valves and easing gear & to state  
ther an approved oil retaining appliance  
itted at the aft end of the stern tube.

They should also be informed that the pumping  
angements are not in accordance with the Rules,  
ich provide that each power bilge pump is to  
arranged to draw from any hold or machinery  
partment of the vessel & that no bilge suction  
be is to be less than 2" bore. They should be  
uested to arrange for the engine bilge pump  
be connected to the main Bilge line by means  
a pipe 2" bore & to advise this office when  
where this alteration is to be made.

L 28/9/23.

R  
28/9/23.

W Lloyd's Register  
Foundation

W123-0266