

COPY.

Lloyd's Register of Shipping.



OF HULL.

Port

26th November, 1931.

C. MOFFATT and W. H. WAGGOTT **This is to Certify** that

the undersigned Surveyors, this Society did at the request of
C. Moffatt and W. H. Waggett on the
 10th, 11th, and 12th of November 1931, for the purpose of
 examining and testing by water pressure, the following solid
 drawn copper pipes made to the order of Messrs. J. Crichton &
 Co., Ltd, Saltney, near Chester, for their Yard No. Y.518

2	Main Steam	3" bore by 8 L.S.G.
1	Steam to Engine Room Auxiliaries.	1½" " " 13 "
3	Blow down.	1" " " 12 "
1	Scum.	1" " " 12 "
1	Steam to Fan and Coils.	1" " " 12 "
1	" " General Service pump	¾" " " 14 "
1	" " Auxiliary pumps and injector.	¾" " " 14 "
1	" " Circulating pump	¾" " " 14 "
1	" " Injection	¾" " " 14 "
1	" " Port Feed pump	¾" " " 14 "
1	" " Starboard feedpump	¾" " " 14 "
1	" " Fan engine	¾" " " 14 "
1	" " Coils (Starboard)	¾" " " 14 "
1	" " Coils. (Port)	¾" " " 14 "

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society."

- | | |
|---------------------------|---------------------|
| 1 steam to Coils | 3/4" bore by 14LSG. |
| 1 " " Oil fuel unit. | 3/4" " " 14 " |
| 2 Main Feed delivery | 1 1/2" " " 12 " |
| 3 Auxiliary feed delivery | 1 1/2" " " 12 " |

A sample of each pipe was subjected to a flattening test and shewed no signs of cracking.
 The steam pipes were tested to 400 lbs. per square inch and the feed pipe to 500 lbs. per square inch and stamped thus *M.* or *W-W* for identification.

C. Moffatt and W. H. D. Aggall

SURVEYORS TO LLOYD'S REGISTER OF SHIPPING.

Fee:- £1.1.0.

