

DECK

Rpt. 11c.

Index No. (For London Office only.)

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.

PARTICULARS IN RESPECT OF STEAM SHIPS HAVING SPAR OR AWNING DECKS.

Port of Survey

Date of Survey

Name of Surveyor

19/8/29

Ship's Name. *S.S. Mexico*

Port of Registry and Nationality.

Official Number.

Gross Tonnage.

Date of Build.

Particulars of Classification.

Number in Register Book

1001. With flat Counterplated

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK Tonnage.
Length on LOADLINE		Frame Depth Rule	Ceiling Sheer	Peak Tanks
CORRECTED DIMENSIONS.	3780			

Moulded Depth as measured ..... 30-3 Main Deck.  
" " " ..... 37-9/2 Spar or Awning Deck.

Addition for Keel below base line for draught record.....inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

Co-efficient of fineness .....

Any modification necessary [Para. 4 (a) to (e)\*]

Co-efficient as corrected .....

. 81

CORRECTION FOR LENGTH:—

Length of Ship on Load Line..... 378.0 ✓  
 Length in Table ..... 363.0  
 Difference ..... 15.0  
 Correction for 10ft. .... 1.8  
 × Difference ÷ 10 = 1.20 ✓  
 + 1/4 ✓

Allowance for strength in excess of Lloyd's rules =

State particulars—

Height of 'Tween Decks.....

(From top of beam to top of beam at side)

Correction for Height of 'Tween Decks in Spar-decked Ships.....

7-6 1/2 - 2800m

Freeboard Table B or C .....

Correction for Length.....

Correction for Height of 'Tween Decks in Spar-decked Ships.....

Correction for Strength in excess of Lloyd's rules.....

Correction for Iron Deck if required.....

Other Corrections (if any).....

4-6 3/4 + 1/4 = 4-8 ✓

- 3/4 4-4 1/2 ✓

4-4 1/2 ✓  
3-10 1/2 ✓

Sheer at Stem ..... at 1/4 length from Stem .....

Sternpost... " " " Sternpost...

Drop in Sheer abaft amidships.....

Round of Spar-deck Beam.....

" " Main-deck " .....

Length × Height. State if open or closed at ends.

Forecastle ..... ×

Bridge..... ×

Poop..... ×

Correction necessary because clearside amidships measured in accordance with the Statute is not taken at intersection of the wood or steel deck with side

Winter Freeboard from Deck Line .....

Summer " " " .....

Indian Summer " " " .....

N.A. Winter " " " .....

30-3 1/2  
3-10 1/2  
26-5 ✓  
mli

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck:—

Fresh Water Line above centre of Disc ...

Indian Summer Line " " " ...

Winter Line below " " " ...

Winter North Atlantic Line " " " ...

NOTE.—All vessels equal in strength to Lloyd's Spar-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for Ships of full scantlings to the upper deck, are to be considered as Spar-decked Ships, the freeboard for which will vary with their strength. All vessels equal in strength to Lloyd's Awning-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for a Spar-decked Vessel, are to be considered as Awning-decked Ships, the freeboard for which will vary with their strength.

\* If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.

