

(LLOYD'S REGISTER.)
VESSELS OF 100 TONS AND UPWARDS.

G.R. 130.
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Special Letters (if any) -----

Official Number.	Name of Ship.	No., Date, and Port of Registry.
160,197.	Victolite.	13/1928 Glasgow.

No., Date, and Port of Previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Motorship Twin Screw.	Linthouse	1928	Alex. Stephen & Sons Ltd, Glasgow.

Number of Decks ...	Two	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	Feet.	Tenths.
Number of Masts ...	Two		510	2.0
Rigged ...	Fore & Aft, Schooner	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	510	0.0
Stern ...	Elliptical		Main breadth to outside of plank plating ...	68
Build ...	Out & In Strakes	Depth in hold from tonnage deck to ceiling at midships ...		---
Galleries ...	None		Depth from top of beam amidships to top of keel ...	38
Head ...	None	Depth from top of deck at side amidships to bottom of keel		38
Framework and description of vessel ...	Steel Oil Tanker		Round of beam ...	1
Number of Bulkheads ...	19	Length of engine room, if any ...	62	0.0
Number of water ballast tanks, and their capacity in tons ...	Five 709 Tons.			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... 23060 Tons. Ditto per inch immersion at same depth ... 72.9 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	B.H.P. per I.H. = Speed of Ship.
Two	Reciprocating Internal Combustion Direct Acting Vertical	Foreign	1928	Fried Krupp Kiel-gaarden Germany	Four 680 m/m	Two cycle		1750 each
Two	Water Tube	British	1927	Babcock & Wilcox Ltd, Renfrew.	single 1300 m/m	90 Revs. per minute.		11 knots

PARTICULARS OF TONNAGE.


GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	10799.51	On account of space required for propelling power	3651.10
Space or spaces between Decks ...	-----	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	482.75
Turret or Trunk ...	-----	These spaces are the following, viz.:—Below Deck & Round Houses	
Forecastle ... (Houses in) ...	37.80	(Number of seamen or apprentices for whom accomodation is certified) 47	
Bridge space (Houses in) ...	62.36	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Poop or Break ...		Gyro Compass Space 2.92	
Side Houses ...		Masters Accommodation 27.65	
Deck Houses ...	305.62	Chart Space 11.91	
Chart House ...	11.91	Wireless Space 5.69	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	192.50	Boatswains Store 75.00	564.66
Excess of Hatchways ...		Ballast Pump Spaces 84.35	
Gross Tonnage ...	11409.70	Steering Gear Space 37.50	
Deductions, as per Contra ...	4698.51	Water Ballast Spaces 319.64	4698.51
Register Tonnage ...	6711.19		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 1296.13 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 279.53 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Forecastle Part 1. L.17.5'	- 26.59 Tons	
Forecastle Part 11. L.21.5'	- 35.48 Tons	33.80 Tons.
Deductions	1.68	
Open Bridge L.33.8'	- 101.40 Tons.	

Name of Master	David George Williams	Certificate of Service No. 007654.
No. of Owners		Competency No.
Name, Residence, and Description of Managing Owner if there are more owners than one.	Imperial Oil, Limited, Toronto, Canada. Sixty-four (64) shares.	David George Williams, c/o Imperial Oil Limited, 56, Church Street, Toronto, Canada - Manager-
Dated	15 Mar. 1928	



W134-0016.1