

Messrs. Howaldtswerke's No. 765.

Plan shewing hatch web carriers submitted, in duplicate,
by the Hamburg Surveyors.

It is submitted the Surveyors be informed that the scantlings and arrangements as shewn will be approved, provided they be carried out to their satisfaction.

With regard to the question of the depths of the webs at Nos. 1 and 3 hatchways in the tween decks it should be pointed out that the depths given, viz. 550 and 460 m/m respectively represent the minimum which could be accepted to comply with the standard of the Rules, ^{with mounting angles of 5° as proposed} and it will be necessary for the ~~depths of the webs to be amended accordingly.~~ If it is desired, in view of the plates being ordered, to adhere to the depths originally proposed by the Builders it will be necessary to increase correspondingly the sizes of the mounting angles, or alternatively to fit a rider plate on the lower mountings.

Ltr. 22/7. Ansd. 30/7
1 plan 1 returned

JKE
30. 7. 37.



© 2021

Lloyd's Register
Foundation

W1352-0155