

(LLOYDS REGISTER.)

G. R. 130
Lloyds Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) J. V. R. B.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
142731	"War Pundit"	436 in 1918. London

No., Date, and Port of Previous Registry (if any). ✓

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship, Screw	Sunderland.	1918	Sir James Caird & Sons Ltd. Deptford Road, Sunderland.

Number of Decks	... One	Length from fore part of stem, under the bowsprit, to the	Feet.	Tenths.
Number of Masts	... One	aft side of the head of the stern post	400	-
Rigged	... Not	Length at quarter of depth from top of weather deck at		
Stern	... Elliptical	side amidships to bottom of keel	399	6
Build	... Clincher	Main breadth to outside of plank	52	4
Galleries	... None	Depth in hold from tonnage deck to ceiling at midships	28	5
Head	... Straight	Depth in hold from upper deck to ceiling at midships, in the		
Framework and description of vessel	Steel Cargo Vessel	case of three decks and upwards	-	-
Number of Bulkheads	... Eleven	Depth from top of beam amidships to top of keel	32	1
Number of water ballast tanks, and their capacity in tons	Two = 202 tons	Depth from top of deck at side amidships to bottom of keel	31	3
		Round of beam	1	1
		Length of engine room, if any	56	3

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel... 10640 Tons. Ditto per inch immersion at same depth... 41.3 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of Sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Triple Expansion direct acting vertical	British	1918	Palmer's Shipbuilding & Iron Co. Ltd.	Three 27"	48"		517 3000 11 1/2 knots
One	Cylindrical vertical	British	1918	Jarrow-on-Tyne	44" 73"			

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	4703.43	On account of space required for propelling power	1775.70
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Turret or Trunk	569.08	These spaces are the following, viz.:—	
Forecastle	4.42	Engineers, Officers & Crew.	196.16
Bridge space	147.39	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Poop or Break	28.03	Cubic Metres	
Side Houses	96.71	Masters Accommodation 49.69	
Deck Houses		Boatwain's Store 29.69	
Chart House		Pump space 4.00	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		Chart Room 4.38	
Excess of Hatchways		Wireless Room	
Gross Tonnage	5549.06	Total	2069.16
Deductions, as per Contra	2069.16		
Registered Tonnage	3479.90		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 752.45 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 130.98 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

open forecastle length 39.8 ft = 76.27 tons
" bridge " 120.8 " = 225.39 "

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	Manager
His Majesty represented by the Shipping Controller London.	
Sixty four Shares.	
Dated	2nd December 1918

ockets to
ds.
Diam
Inc

proved.
Angus.
P 6 x 3 1/2
10 3/4
L 7 x 3
P x 1/60
3 1/2 3 1/2 1/4

heir

2.0 ft.

n as il

capacity.
ns.

URGENT



© 2021

Lloyd's Register
Foundation.

59

Signature

D. J. Cusack