

Steam Trawler "R.R.S";

No.24103 in the Register Book;

ons gross;

Built in 1913-5 mo;

:- R. Sutton.

ed:- 100A  
steam trawler 5.13.

LMC. 6.13.

The Ipswich Surveyors recently reported that this vessel had submitted there for Special Survey No.1, and some minor alterations had been carried out. As they further stated that the vessel was being employed in carrying general cargoes on the coast, they were informed that to entitle the vessel to have the 100A.class, the bulkhead at the fore end of machinery space and require to be strengthened, suitable hatchway coamings and ports provided, the pillaring throughout made in accordance with Rules and the machinery casings to be made 7 feet in height above the deck.

It was further considered that a forecastle should be fitted, the equipment made up to the full requirements for cargo vessels.

In reply, the Surveyors stated that the Owners did not wish to have the full 100A.class, and were not prepared to carry out structural alterations.

In the circumstances, the Classing Committee decided to withdraw the vessel's class from the Register Book, and insert three dots (...) in lieu, indicating withdrawal of class at Owner's request.

*W. M.*  
15.1.20.



© 2021

Lloyd's Register  
Foundation

W1565-0006