


For the information of Surveyors and the Committee only.

Received at _____ Office, _____ 19__



Lloyd's Register of Shipping.

(Report on Vessel No. _____ Port _____)

No. 2550 SHIP ~~FORGINGS~~ OR CASTINGS.

The words FORGINGS or CASTINGS, IRON or STEEL, should be struck out as may be required.

I have to report that the undermentioned ~~Iron or Steel Forgings or Castings~~, manufactured by Messrs. *Wm Beardmore & Co Ltd* of *Glasgow* for the Vessel No. *11*, being built by Messrs. *Furness Shipbuilding Co* of *Middlesbrough* have been inspected by me as set forth below and found to be, so far as can be seen, *Sound & free from flaws.*

First Stem Delivered.

Mark on Forgings or Castings.

Lloyd's
No. 2550
18-10-18

Glasgow 10th Dec 1918.
For Fabricated Ship "N" Type *A. W. M. S. M. S. M. S.*

	STERN FRAME.	RUDDER FRAME.	STEM.
Material*			<i>Cast Steel</i>
How made			<i>Open Hearth</i>
Dimensions			<i>Top patterns</i>
Progress on Inspection			<i>Assembled</i>
Date when Inspected			<i>7-9-18 to 18-10-18</i>
CASTINGS.			
Tests on Standard Test Pieces.			<i>N°124 N°139 N°138</i>
Tensile Test—			
Tons per square inch			<i>30.4 28.8 28.0</i>
Extension per cent.			<i>34 35 20</i>
Cold Bending Test—			
Angle before fracture			<i>180° 180° 180°</i>
Drop Test—			
Height from ground			<i>8ft. 8ft. 8ft.</i>
Hammering Test—			
If made according to Rules and found satisfactory			<i>Yes Yes Yes</i>

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

	Tons
<i>Bottom Part</i>	<i>2. 17. 2. 14</i>
<i>Middle Part</i>	<i>0. 18. 1. 13</i>
<i>Top Part</i>	<i>0. 19. 1. 5</i>
	<i>4. 18. 1. 4 = Total Weight.</i>

Fee (if any chargeable) £ *Nil.* Standard Ship.

To be paid at _____

* If of Iron, state whether scrap or puddled Iron. If of steel, state whether made on the Open Hearth process.

